

Sound Advice

ACOUSTICS LTD

REPORT REFERENCE:

SA – 5785-3

ENVIRONMENTAL NOISE IMPACT ASSESSMENT

ProPG Planning and Noise

British Standard 8233: 2014

World Health Organisation (WHO)

CLIENT:

Persimmon Homes

SITE:

Land East of Crofton Cemetery & West of Peak Lane,

Oakcroft Lane

Stubbington

Hampshire

SURVEY DATES:

15th – 20th November 2018

Report By



Mr. B. J. Scrivener MIOA.

Sound Advice Acoustics Ltd

2 West Links, Tollgate, Chandlers Ford, Hampshire, SO53 3TG

Tel: 02380 641357

soundadviceacoustics.co.uk

1 EXECUTIVE SUMMARY	5
1.1 INSTRUCTION	5
1.2 SCOPE OF REPORT.....	5
1.3 SUMMARY OF RESULTS	5
1.3.1 <i>Background Noise Levels.</i>	5
1.3.2 <i>Corrected Noise Levels</i>	5
1.4 POTENTIAL FAÇADE NOISE LEVELS.....	6
1.4.1 <i>Daytime (07:00-23:00)</i>	6
1.4.2 <i>Night Time (23:00-07:00)</i>	6
1.5 RISK ASSESSMENT.....	6
1.5.1 <i>Daytime (07:00-23:00)</i>	6
1.5.2 <i>Night Time (23:00-07:00)</i>	6
1.6 CONCLUSION.....	7
2 INTRODUCTION.....	8
2.1 PLANNING PRACTICE GUIDANCE AND NOISE.....	8
2.1.1 <i>Professional Practice Guidance on Planning & Noise.</i>	9
2.2 BRITISH STANDARD 8233: 2014.....	10
2.3 NATIONAL PLANNING POLICY FRAMEWORK 2019 (NPPF) AND NOISE POLICY STATEMENT FOR ENGLAND 2010 (NPSE).	11
2.3.1 <i>“Significant adverse” and “adverse”</i>	11
2.3.2 <i>NOEL – No Observed Effect Level.....</i>	11
2.3.3 <i>LOAEL – Lowest Observed Adverse Effect Level</i>	11
2.3.4 <i>SOAEL – Significant Observed Adverse Effect Level</i>	11
2.4 WORLD HEALTH ORGANISATION ‘GUIDELINES FOR COMMUNITY NOISE’	11
3 SITE LOCATION.....	12
3.1 PROPOSED DEVELOPMENT.....	13
4 PROPOSED STUBBINGTON BYPASS	15
4.1 CORRECTED NOISE LEVELS.....	17
5 PROCEDURE	18
6 APPARATUS	19
7 RESULTS	20
7.1 DOWNLOADED RESULTS, AND AVERAGES.	20
7.1.1 <i>Position 1 – 15th – 16th November 2018.....</i>	20
7.1.2 <i>Position 1 – 16th – 17th November 2018.....</i>	20
7.1.3 <i>Position 1 – 17th – 18th November 2018.....</i>	20
7.1.4 <i>Position 1 – 18th – 19th November 2018.....</i>	20
7.1.5 <i>Position 1 – 19th – 20th November 2018.....</i>	20
7.1.6 <i>Position 2 – 15th – 16th November 2018.....</i>	21
7.1.7 <i>Position 2 – 16th – 17th November 2018.....</i>	21
7.1.8 <i>Position 2 – 17th – 18th November 2018.....</i>	21
7.1.9 <i>Position 2 – 18th – 19th November 2018.....</i>	21
7.1.10 <i>Position 2 – 19th – 20th November 2018.....</i>	21
7.1.11 <i>Position 3 – 15th – 16th November 2018.....</i>	22
7.1.12 <i>Position 3 – 16th – 17th November 2018.....</i>	22
7.1.13 <i>Position 3 – 17th – 18th November 2018.....</i>	22
7.1.14 <i>Position 3 – 18th – 19th November 2018.....</i>	22
7.1.15 <i>Position 3 – 19th – 20th November 2018.....</i>	22
7.1.16 <i>Position 1 – 15th – 20th November 2018.....</i>	23
7.1.17 <i>Position 2 – 15th – 20th November 2018.....</i>	23
7.1.18 <i>Position 3 – 15th – 20th November 2018.....</i>	23
7.1.19 <i>Corrected Noise Levels</i>	24
7.1.20 <i>Position 1 – 15th – 20th November 2018.....</i>	24
7.1.21 <i>Position 2 – 15th – 20th November 2018</i>	24

7.1.22 Position 3 – 15 th – 20 th November 2018.....	24
8 PROPG PLANNING & NOISE STAGE 1.....	25
8.1 STAGE 1: INITIAL SITE NOISE RISK ASSESSMENT	25
8.2 POTENTIAL FAÇADE NOISE LEVELS.....	26
8.2.1 Daytime (07:00-23:00).....	26
8.2.2 Night Time (23:00-07:00).....	26
8.3 RISK ASSESSMENT.....	26
8.3.1 Daytime (07:00-23:00).....	26
8.3.2 Night Time (23:00-07:00).....	26
9 PROPG PLANNING & NOISE STAGE 2 - ELEMENT 1 – GOOD ACOUSTIC DESIGN	27
10 ELEMENT 2 – INTERNAL NOISE LEVEL GUIDELINES	28
10.1 DISCUSSION OF RESULTS	28
10.2 EXISTING NOISE LEVELS – DAYTIME (07:00 – 23:00)	28
10.3 EXISTING NOISE LEVELS – NIGHT TIME (23:00 – 07:00)	28
10.4 PROPOSED NOISE LEVELS – DAYTIME (07:00 – 23:00)	29
10.5 PROPOSED NOISE LEVELS – NIGHT TIME (23:00 – 07:00)	29
10.6 RECOMMENDATIONS.....	30
10.7 CALCULATION PROCEDURE TO BS 8233: 2014.....	31
10.8 GROUND FLOOR LOUNGE	31
10.9 TOP FLOOR BEDROOM.....	32
10.10 VENTILATION (D_{NE}).....	33
10.11 GLAZING (R_{WI}).....	33
10.12 WALLS (R_{EW}).....	33
10.13 ROOF (R_{RR}).....	33
10.14 GLAZING & VENTILATION ASSESSMENT	33
10.15 NIGHT NOISE GUIDELINES EUROPE 2009	34
11 ELEMENT 3 – EXTERNAL AMENITY AREA NOISE ASSESSMENT	36
11.1 OUTDOOR LIVING AREAS.....	36
12 ELEMENT 4 – ASSESSMENT OF OTHER RELEVANT ISSUES	38
13 ACOUSTIC DESIGN STATEMENT.....	39
14 RECOMMENDATION TO DECISION MAKER.....	40
15 CONCLUSION	41
15.1 BACKGROUND NOISE LEVELS.....	41
15.1.1 Corrected Noise Levels	41
15.2 POTENTIAL FAÇADE NOISE LEVELS.....	41
15.2.1 Daytime (07:00-23:00).....	41
15.2.2 Night Time (23:00-07:00).....	41
15.3 RISK ASSESSMENT.....	41
15.3.1 Daytime (07:00-23:00).....	41
15.3.2 Night Time (23:00-07:00).....	42
15.4 CONCLUSION.....	42
16 UNCERTAINTY	43
16.1 UNCERTAINTY BUDGET	43
17 RESULTS	44
17.1 15 TH – 16 TH NOVEMBER 2018 POSITION 1.....	44
17.2 16 TH – 17 TH NOVEMBER 2018 POSITION 1.....	45
17.3 17 TH – 18 TH NOVEMBER 2018 POSITION 1.....	46
17.4 18 TH – 19 TH NOVEMBER 2018 POSITION 1.....	47
17.5 19 TH – 20 TH NOVEMBER 2018 POSITION 1.....	48
17.6 15 TH – 16 TH NOVEMBER 2018 POSITION 2.....	49
17.7 16 TH – 17 TH NOVEMBER 2018 POSITION 2.....	50
17.8 17 TH – 18 TH NOVEMBER 2018 POSITION 2.....	51
17.9 18 TH – 19 TH NOVEMBER 2018 POSITION 2.....	52

17.10	19 TH – 20 TH NOVEMBER 2018 POSITION 2.....	53
17.11	15 TH – 16 TH NOVEMBER 2018 POSITION 3.....	54
17.12	16 TH – 17 TH NOVEMBER 2018 POSITION 3.....	55
17.13	17 TH – 18 TH NOVEMBER 2018 POSITION 3.....	56
17.14	18 TH – 19 TH NOVEMBER 2018 POSITION 3.....	57
17.15	19 TH – 20 TH NOVEMBER 2018 POSITION 3.....	58
18	ENVIRONMENTAL CONDITIONS	59

1 EXECUTIVE SUMMARY

1.1 Instruction

Sound Advice Acoustics Ltd have been instructed by Persimmon Homes Thames Valley to undertake a background noise survey to British Standard 8233: 2014 to determine the impact of existing noise sources on the proposed accommodation scheme, Land East of Crofton Cemetery & West of Peak Lane, Oakcroft Lane, Stubbington, Hampshire. Influence of the recently approved Stubbington Bypass is also to be taken into account within the calculations to future proof the proposed residential dwellings from increased road traffic noise.

1.2 Scope of Report

The measurements will be undertaken in accordance with ISO 1996 – Part 2: 2017 to determine the existing background noise levels and British Standard 8233: 2014 will be used to determine the impact of existing traffic on the internal noise environment within the proposed residential dwellings. This report aims to establish the following:

- Existing background noise levels within the area;
- Assess the potential internal noise levels on the proposed rooms;
- Provide specifications for the ventilation and window glazing with the proposed rooms.
- Take into account the proposed Stubbington Bypass within the BS 8233: 2014 Calculations.

1.3 Summary of Results

1.3.1 Background Noise Levels

A background noise survey was undertaken from 15th – 20th November 2018 at three positions, front, rear and side of site in order to establish the underlying background noise levels. The maximum day time levels for each position are tabulated below:-

Assessment Position	Date Start	Date Finish	Daytime LAeq	Night Time LAeq
Position 1 Front	15/11/2018	20/11/2018	54.3	46.6
Position 2 Side	15/11/2018	20/11/2018	57.2	47.2
Position 3 Rear	15/11/2018	20/11/2018	54.3	53.3

1.3.2 Corrected Noise Levels

The following table demonstrates the resultant noise levels corrected for the worst case scenario of +5 dB correction for the Stubbington Bypass Increase as per the Hampshire County Council Transport Business Case – April 2016 Page 84.

Assessment Position	Date Start	Date Finish	Daytime LAeq	Night Time LAeq
Position 1 Front	15/11/2018	20/11/2018	59.3	51.6
Position 2 Side	15/11/2018	20/11/2018	62.2	52.2
Position 3 Rear	15/11/2018	20/11/2018	59.3	58.3

1.4 Potential Façade Noise Levels

1.4.1 Daytime (07:00-23:00)

Time Period	Highest Potential Façade Noise Level	Noise Risk Category
Average Daytime (07:00-23:00)	$L_{Aeq, 16\text{ HOUR}}$ 62 dB	1 – Low 50 – 63 dB

1.4.2 Night Time (23:00-07:00)

Time Period	Highest Potential Façade Noise Level	Noise Risk Category
Average Night Time (23:00-07:00)	$L_{Aeq, 16\text{ HOUR}}$ 58 dB	2 – Medium 55 – 60 dB
	Maximum (10 Times) – L_{Amax} 78.6 dB	>80 dB (10 Times in 8 Hours)

1.5 Risk Assessment

1.5.1 Daytime (07:00-23:00)

Risk Assessment Category	Risk Assessment
1 – Low	At low noise levels, the site is likely to be acceptable from a noise perspective provided that a good acoustic design process is followed and is demonstrated in an ADS which confirms how the adverse impacts of noise will be mitigated and minimised in the finished development.

1.5.2 Night Time (23:00-07:00)

Risk Assessment Category	Risk Assessment
2 – Medium	As noise levels increase, the site is likely to be less suitable from a noise perspective and any subsequent application may be refused unless a good acoustic design process is followed and is demonstrated in an ADS which confirms how the adverse impacts of noise will be mitigated and minimised, and which clearly demonstrate that a significant adverse noise impact will be avoided in the finished development.

The above table demonstrates this site is located within Noise Risk Category 1 which suggests a low level of risk for daytime levels and Noise Risk Category 2 which suggests a Medium level of risk for night time levels. Therefore, further mitigation levels will be required at Stage 2.

1.6 CONCLUSION

Dwellings on the proposed development will require a standard 4mm glass / 16mm air gap / 4mm glass double glazed windows and a standard trickle vents.

The above should be implemented to all rooms to ensure the internal noise levels are acceptable in terms of the assessment to British Standard 8233: 2014. This also takes into account the corrected values for the proposed Stubbington Bypass.

The guideline has been considered acceptable criteria for this assessment given the sites geographical location and proximity to a potential major trunk road (New Stubbington Bypass). The layout has been designed in order to allow for acoustics and minimise the noise levels within the outdoor living spaces. The calculation demonstrates the external living spaces surrounding the houses are likely to see noise levels below the lower guideline of 50 dB.

Levels have been recorded and assessments made in accordance with the relevant standards. Internal criteria's have been set and calculations made in order to determine the minimum construction details required in order to meet the desired level within the proposed residential dwellings and satisfy the local council's requirements.

National Planning Policy Framework 2019 suggests that planning permission should be granted unless any adverse impacts of doing so would significantly and demonstrably outweigh the benefits, when assessed against the policies in the framework taken as a whole, or specific policies in the framework indicate the application should be restricted.

Based on the calculations and assessments made within this report it is the professional opinion of Sound Advice Acoustics Ltd that the proposed development can demonstrate compliance with the National Planning Policy Framework 2018, NPPF & NPSE and that, with regards to sound, planning permission can be granted.

2 INTRODUCTION

Sound Advice Acoustics Ltd have been instructed by Persimmon Homes Thames Valley to undertake a background noise survey to British Standard 8233: 2014 to determine the impact of existing noise sources on the proposed accommodation scheme, Land East of Crofton Cemetery & West of Peak Lane, Oakcroft Lane, Stubbington, Hampshire. Influence of the recently approved Stubbington Bypass is also to be taken into account within the calculations to future proof the proposed residential dwellings from increased road traffic noise.

Ambient noise levels were measured between 15th – 20th November 2018. This report by Sound Advice Acoustics Ltd gives the results of these measurements and an assessment in accordance with government planning guidelines and relevant standards together with mitigation measures as required.

With regards to external ambient noise, environmental noise levels are be monitored at the site in accordance with British Standard 7445: 2003 'Description and measurement of environmental noise assessments and assessments made in-line with ProPG: Planning and Noise.'

2.1 Planning Practice Guidance and Noise

March 2014 saw the publication of the Planning Practice Guidance for Noise (PPG-Noise) and this was subsequently updated in December 2014. The Planning Practice Guidance and Noise sets out details of how potential noise impacts should be evaluated.

'Local planning authorities' plan-making and decision taking should take account of the acoustic environment and in doing so consider:

- ✓ whether or not a significant adverse effect is occurring or likely to occur;
- ✓ whether or not an adverse effect is occurring or likely to occur; and
- ✓ whether or not a good standard of amenity can be achieved.

In line with the Explanatory Note of the Noise Policy Statement for England, this would include identifying whether the overall effect of the noise exposure (including the impact during the construction phase wherever applicable) is, or would be, above or below the significant observed adverse effect level and the lowest observed adverse effect level for the given situation. As noise is a complex technical issue, it may be appropriate to seek experienced specialist assistance when applying this policy.'


In accordance with Stage 2: Full Assessment, Other Noise Sources, detailed calculations and assessments should be carried out pertaining to these as PPG Noise does not provide advice and guidance when taking these elements into consideration.

2.1.1 Professional Practice Guidance on Planning & Noise.

The Professional Practice Guidance (ProPG) on Planning and Noise for New Residential Development was published in May 2017 by the Association of Noise Consultants (ANC), Institute of Acoustics (IOA) and Chartered Institute of Environmental Health (CIEH). This document was developed in order to offer professional guidance on recommended strategies to the management of noise for use in the associated planning applications for specific sites. This furthermore, provides a numerical acoustic standard in accordance with the Government's planning and noise policies.

This document has been developed to ensure the developer adopts a good acoustic design process to ensure protection for future residents from the potential harmful effects from noise. The ProPG denotes that it '*does not constitute an official government code of practice and neither replaces nor provides an authoritative interpretation of the law or government policy on which users should take their own advice as appropriate*'.

The ProPG adopts a twin-stage approach, firstly providing an 'Initial Noise Risk Assessment' of the proposed development site before undertaking a detailed approach of a noise impact assessment. The results from the initial noise risk assessment are an indication of the general acoustic environment of the proposed development and demonstrate how detailed the noise impact assessment will need to be in order to mitigate any acoustic issues.



2.2 British Standard 8233: 2014

Calculations are to be made in accordance with BS 8233: 2014 Sound Insulation and Noise Reduction for Buildings Code of Practice.

BS 8233: 2014 set the following parameters as target levels that should be designed to within rooms such as Living Rooms and Bedrooms.

Indoor ambient noise levels in spaces when they are unoccupied and privacy is also important		
Objective	Typical situations	Design Range $L_{Aeq,t}$ dB
Typical noise levels for acoustic privacy in shared spaces	Living room	35 – 40
NOTE: See Noise control in building services [28] and BS EN ISO 3382.		

Indoor ambient noise levels for dwellings			
Activity	Location	07:00 – 23:00	23:00 – 07:00
Resting	Living Room	35 dB L_{Aeq} 16 HOUR	--
Dining	Dining Room / Area	40 dB L_{Aeq} 16 HOUR	--
Sleeping (daytime resting)	Bedroom	35 dB L_{Aeq} 16 HOUR	30 dB L_{Aeq} 8 HOUR

Calculations and assessments are therefore to be carried out in order to satisfy the above requirements of BS8233: 2014.

2.3 National Planning Policy Framework 2019 (NPPF) and Noise Policy Statement for England 2010 (NPSE).

References and evaluations are to be made to the National Planning Policy Framework 2019 (NPPF) and the Noise Policy Statement for England 2010 (NPSE). The purpose of this document is to include all aspects of environmental noise within assessments i.e. environmental noise, neighbour noise and neighbourhood noise. Noise is to be considered alongside other relevant issues relating to the site and should not be considered in isolation, according to the NPSE.

There are several key phrases within the NPSE aims and these are discussed below.

2.3.1 “Significant adverse” and “adverse”

There are two established concepts from toxicology that are currently being applied to noise impacts, for example, by the World Health Organisation. They are:

2.3.2 NOEL – No Observed Effect Level

This is the level below which no effect can be detected. In simple terms, below this level, there is no detectable effect on health and quality of life due to the noise.

2.3.3 LOAEL – Lowest Observed Adverse Effect Level

This is the level above which adverse effects on health and quality of life can be detected.

Extending these concepts for the purpose of this NPSE leads to the concept of a significant observed adverse effect level.

2.3.4 SOAEL – Significant Observed Adverse Effect Level

This is the level above which significant adverse effects on health and quality of life occur.

It is not possible to have a single objective noise-based measure that defines SOAEL that is applicable to all sources of noise in all situations. Consequently, the SOAEL is likely to be different for different noise sources, for different receptors and at different times. It is acknowledged that further research is required to increase our understanding of what may constitute a significant adverse impact on health and quality of life from noise. However, not having specific SOAEL values in the NPSE provides the necessary policy flexibility until further evidence and suitable guidance is available.

2.4 World Health Organisation ‘Guidelines for Community Noise’

In addition, calculations are to be made for the predicted daytime noise levels within the outdoor living area and assessments made against the recommended levels within the World Health Organisation’s ‘Guidelines for Community Noise’. In order to evaluate these levels accurately, the 3D modelling software CADNA A is to be adopted for the purpose of this assessment.

Finally, assessments and references are to be made to the World Health Organisation Night Time Noise Guidance 2009.

3 SITE LOCATION


Position of Site in Wider Area

The site is located in Stubbington just south of the proposed Bypass noise source is road traffic noise.



3.1 Proposed Development

The proposed development is shown below together with the proposed Bypass.





Schedule of Accommodation

Private						
House Type	Beds	GIA (sq ft)	Storeys	No.	Total (sq ft)	Mix
Athens	2	638	2	2	1,276	25.5%
Hanbury	2*	671	2	27	20,547	
Chatworth	3	918	2	3	2,754	
Souter	3	912	2.5	18	16,778	
Chester	3	927	2.5	14	13,138	50.5%
Hawfield	3	969	2	5	4,845	
Clayton	3	999	2	17	10,983	
Windsor	2	1197	2	10	11,970	
Lumley	4	1220	2.5	7	8,540	23.2%
Chedworth	4	1222	2	3	3,666	
Sub Total:				112	108,197	
Private Total:						

Private Total:						
House Type	Beds	GIA (sq ft)	Storeys	No.	Total (sq ft)	Mix
Kingston	2	630	2	2	1,260	33.3%
Marlborough	4	1513	2	3	4,539	
Marylebone	4	1623	2	3	4,869	66.7%
Windsor	4	1843	2	2	3,726	
Sub Total:				15	22,795	
Private Total:						

Shared Ownership						
House Type	Beds	GIA (sq ft)	Storeys	No.	Total (sq ft)	Mix
Alnwick	2	638	2	14	8,932	50.0%
Chester	3	974	2	14	12,296	50.0%
Shared Total:				28	21,168	50.0%
Affordable Mix:						34.1%

Affordable Rented						
House Type	Beds	GIA (sq ft)	Storeys	No.	Total (sq ft)	Mix
1BF	1	487	1	4	1,988	7.4%
2BF	2	613	2	12	7,306	22.2%
3BF	2	631	2	16	10,096	33.3%
Chester	3	874	2	18	15,732	33.3%
4BH	4	1084	2	4	4,336	7.4%
Affordable Total:				54	39,568	29.5%
Affordable Mix:						34.5%

Affordable Housing Sub Total:			
	No.	Total (sq ft)	Mix
(Discount Market / Shared Ownership / Affordable Rented)	62	60,676	39.2%

Overall Site Total:

PLOTS Total: 209 Total (sq ft) 191,863



D 25.02.20 see planning cover note br db

C 20.09.19 see planning cover note br db

B 22.07.19 see planning cover note dated 23 July br db

A 14.05.19 4.2m roads widened to 6.6m and 3.6m parking br db

Rev Date Revision Details Dr Ch

Job Title Oakcroft Lane, Stubbington

Drawing Title

Tenure Plan

Job No 220 Drawing No A-02-010-TP Rev D

Drawn Checked Date

BR DB March '19

Scale 1:1000 @ A1 / 1:2000 @ A3

metres 20 40 60 80 100

Status PLANNING

File Location A technical manual sheet detailing calculations and drawings

Acoustic Consultants and Engineers

© Persimmon Homes. No drawings to be scaled from drawing except for the purposes of Planning Applications. The contractor should check all dimensions on site. It is the contractors responsibility to ensure compliance with Building Regulations. No drawings should be copied or modified without permission from Persimmon Homes.

4 PROPOSED STUBBINGTON BYPASS

A proposal has been made for a Bypass to be constructed and at time of this report being issued, the Bypass is subject to a Public Enquiry. However, the Bypass is to be taken into account within the calculations in order to future proof the proposed development.

The following extract has been taken from the Environmental Impact Assessment carried out on behalf of Hampshire County Council and was included within their Hampshire County Council Transport Business Case – April 2016



Noise

- 3.7.24 Noise implications of the scheme are generally defined in terms of the change in levels of noise annoyance experienced by people. The two main factors which have the potential to affect noise levels in relation to this scheme are changes in traffic flows / patterns / speeds and proximity of receptors to the line of the route.
- 3.7.25 During construction of the scheme potentially significant noise and vibration impacts could occur in a worst case scenario. The use of mitigation measures will make sure that most of the construction work would have a small negative impact or no impact; although there is a chance that negative impacts could occur during some of the works.
- 3.7.26 The noise assessment undertaken for the EIA identifies that there are a number of areas - particularly along Titchfield Road (south of the scheme), Peak Lane, Rowan Way, Stubbington Lane and Gosport Road (west of the scheme) - that will experience a significant reduction in noise levels. However, there are also areas that are predicted to have a significant increase in noise levels and where mitigation measures are therefore required.




Figure 3-3: Predicted changes in noise¹⁶

¹⁶ Source: Stubbington Bypass Environmental Statement (WSP / PB, June 2015)




Figure 1-1: Locational context of the Stubbington Bypass scheme

PROPOSED BYPASS & PROPOSED RESIDENTIAL DEVELOPMENT



4.1 Corrected Noise Levels

The following table demonstrates the resultant noise levels corrected for the worst case scenario of +5 dB correction for the Stubbington Bypass Increase as per the Hampshire County Council Transport Business Case – April 2016 Page 84.

Assessment Position	Date Start	Date Finish	Daytime LAeq	Night Time LAeq
Position 1 Front	15/11/2018	20/11/2018	59.5	51.6
Position 2 Side	15/11/2018	20/11/2018	62.2	52.2
Position 3 Rear	15/11/2018	20/11/2018	59.3	58.3

5 PROCEDURE

External noise levels were recorded over a typical period and analysis date extrapolated between 07:00 hrs 15th and 20th November 2018 at position 1, 2 & 3 as detailed on the attached plan sketch layout.

Sample measurements were recorded over continuous 15 minute samples and from this data the hourly LAeq daytime values have been evaluated. Sound Pressure Levels were recorded on the following setting along with a full octave band frequency analysis measured simultaneously and between 31.5 Hz and 16.0 kHz.

<u>Daytime 07:00 – 23:00</u>		<u>Night Time 23:00 – 07:00</u>	
$L_{Aeq\ 1\ HOUR}\ dB$	$L_{A10\ 1\ HOUR}\ dB$	$L_{Aeq\ 15\ MINUTES}\ dB$	$L_{A10\ 15\ MINUTES}\ dB$
$L_{AMAX\ 1\ HOUR}\ dB$	$L_{A50\ 1\ HOUR}\ dB$	$L_{AMAX\ 15\ MINUTES}\ dB$	$L_{A50\ 15\ MINUTES}\ dB$
$L_{AMIN\ 1\ HOUR}\ dB$	$L_{A90\ 1\ HOUR}\ dB$	$L_{AMIN\ 15\ MINUTES}\ dB$	$L_{A90\ 15\ MINUTES}\ dB$

Calculations have been made in accordance with BS 8233: 2014 ‘Sound Insulation and Reduction of Buildings - Code of Practice’. Recommendations were made for any additional acoustics measures to conform to these standards.

From the downloaded recorded results, the daytime and night time periods were assessed and used within the above calculations as $L_{Aeq\ 16\ HOUR}\ dB$ levels for daytime and $L_{Aeq\ 8\ HOUR}\ dB$ levels for night time. These are detailed within this report. All data averaged throughout the day has been done so on a logarithmic basis to give accurate $L_{Aeq\ 16\ Hour}\ dB$ daytime and $L_{Aeq\ 8\ Hour}\ dB$ night time noise levels.

Finally, it should be noted that calculations are carried out with façade levels corrected from the recorded noise levels to the calculated façade levels.

6 APPARATUS

The equipment was calibrated using a sound pressure level of 114.0 dB at an octave band centre frequency of 1000Hz with reference to 2×10^{-5} Nm⁻² before and after the tests and the equipment set to have no inaccuracy greater than 0.2dB.

All the following equipment was calibrated in accordance with the laboratory accreditation requirements of the United Kingdom Accreditation Service (UKAS) on the following dates. Calibration schedules are implemented within Sound Advice Acoustics Ltd in accordance with UKAS directive LAB 23.

118 NOISE METER s/n 31471 ENVIRONMENTAL TESTING - HELEN

Description	Make	Type	Serial No.	Calibration Intervals	Last Calibrated	Next Due Calibration
Integrated Sound Level Meter	Norsonic	118	31471	2 YEARS	25.09.2018	25.09.2020
12.5mm Microphone (with windshield)	Norsonic	1225	57535	2 YEARS	25.09.2018	25.09.2020
Microphone Pre – Amplifier	Norsonic	1206	30687	2 YEARS	25.09.2018	25.09.2020

140 NOISE METER s/n 1402941 ENVIRONMENTAL TESTING - SUSAN

Description	Make	Type	Serial No.	Calibration Intervals	Last Calibrated	Next Due Calibration
Integrated Sound Level Meter	Norsonic	140	1402941	2 YEARS	12.06.2018	12.06.2020
12.5mm Microphone (with windshield)	Norsonic	GRAS 40AF	179711	2 YEARS	12.06.2018	12.06.2020
Microphone Pre – Amplifier	Norsonic	1209	30479	2 YEARS	12.06.2018	12.06.2020

Rion NL – 52 s/n 00242696 ENVIRONMENTAL TESTING - GWEN

Description	Make	Type	Serial No.	Calibration Intervals	Last Calibrated	Next Due Calibration
Integrated Sound Level Meter	Rion	NL-52	00242696	2 YEARS	02.05.2018	02.05.2020
Microphone (with windshield)	Rion	UC-59	06178	2 YEARS	02.05.2018	02.05.2020
Microphone Pre – Amplifier	Rion	NH-25	32724	2 YEARS	02.05.2018	02.05.2020

Full calibration certificates are available upon request.

7 RESULTS

$L_{Aeq,t}$ -	The equivalent A weighted sound pressure level recorded over a time interval of 5 minutes night time and 1 hourly daytime.
L_{Amax} -	The maximum A weighted sound pressure level recorded over a time interval of 5 minutes night time and 1 hourly daytime.

7.1 Downloaded results, and averages.

7.1.1 Position 1 – 15th – 16th November 2018

NOISE LEVEL SUMMARY ASSESSMENT			Octave Band Centre Frequency (Hz)									
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0k	2.0k	4.0k	8.0k	16.0k
DAYTIME 07:00 - 23:00 <small>LAeq 16 HOUR & Corresponding LAmax 16 HOUR</small>	53.9	79.9	58.6	56.9	51.5	51.8	51.1	49.7	45.5	39.4	39.3	22.1
NIGHT TIME 23:00 - 07:00 <small>LAeq 8 HOUR & Corresponding LAmax 8 HOUR</small>	46.4	81.5	49.3	47.7	41.1	41.3	43.3	41.7	39.4	34.6	32.9	18.3

7.1.2 Position 1 – 16th – 17th November 2018

NOISE LEVEL SUMMARY ASSESSMENT			Octave Band Centre Frequency (Hz)									
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0k	2.0k	4.0k	8.0k	16.0k
DAYTIME 07:00 - 23:00 <small>LAeq 16 HOUR & Corresponding LAmax 16 HOUR</small>	54.2	83.7	57.5	56.1	52.4	50.8	50.9	49.3	46.4	42.7	43.0	26.9
NIGHT TIME 23:00 - 07:00 <small>LAeq 8 HOUR & Corresponding LAmax 8 HOUR</small>	40.6	70.3	49.6	47.5	42.7	39.6	36.4	34.3	31.7	31.7	31.0	15.7

7.1.3 Position 1 – 17th – 18th November 2018

NOISE LEVEL SUMMARY ASSESSMENT			Octave Band Centre Frequency (Hz)									
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0k	2.0k	4.0k	8.0k	16.0k
DAYTIME 07:00 - 23:00 <small>LAeq 16 HOUR & Corresponding LAmax 16 HOUR</small>	50.1	83.0	58.1	55.7	49.4	47.5	49.0	44.9	38.3	38.5	38.3	21.0
NIGHT TIME 23:00 - 07:00 <small>LAeq 8 HOUR & Corresponding LAmax 8 HOUR</small>	39.1	71.6	51.1	46.8	40.5	39.4	36.7	34.3	28.6	26.6	23.4	11.1

7.1.4 Position 1 – 18th – 19th November 2018

NOISE LEVEL SUMMARY ASSESSMENT			Octave Band Centre Frequency (Hz)									
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0k	2.0k	4.0k	8.0k	16.0k
DAYTIME 07:00 - 23:00 <small>LAeq 16 HOUR & Corresponding LAmax 16 HOUR</small>	48.1	75.0	56.8	54.1	49.8	48.8	46.6	42.2	34.1	36.5	36.5	16.5
NIGHT TIME 23:00 - 07:00 <small>LAeq 8 HOUR & Corresponding LAmax 8 HOUR</small>	46.6	80.6	54.7	49.3	43.1	44.0	43.5	42.8	38.8	31.4	30.5	16.9

7.1.5 Position 1 – 19th – 20th November 2018

NOISE LEVEL SUMMARY ASSESSMENT			Octave Band Centre Frequency (Hz)									
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0k	2.0k	4.0k	8.0k	16.0k
DAYTIME 07:00 - 23:00 <small>LAeq 16 HOUR & Corresponding LAmax 16 HOUR</small>	54.5	80.3	62.6	59.0	51.1	52.2	51.7	50.4	46.2	39.1	39.6	24.2
NIGHT TIME 23:00 - 07:00 <small>LAeq 8 HOUR & Corresponding LAmax 8 HOUR</small>	46.3	79.7	53.7	49.7	42.7	44.1	43.0	42.9	38.0	28.5	25.6	13.4

7.1.6 Position 2 – 15th – 16th November 2018

NOISE LEVEL SUMMARY ASSESSMENT			Octave Band Centre Frequency (Hz)									
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0k	2.0k	4.0k	8.0k	16.0k
DAYTIME 07:00 - 23:00 LAeq 16 HOUR & Corresponding LAmax 16 HOUR	54.8	78.2	27.0	37.4	39.4	45.0	48.9	51.0	49.0	42.3	40.7	15.9
NIGHT TIME 23:00 - 07:00 LAeq 8 HOUR & Corresponding LAmax 8 HOUR	42.9	76.0	14.6	24.9	25.4	30.8	36.7	39.2	37.0	31.3	28.6	8.8

7.1.7 Position 2 – 16th – 17th November 2018

NOISE LEVEL SUMMARY ASSESSMENT			Octave Band Centre Frequency (Hz)									
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0k	2.0k	4.0k	8.0k	16.0k
DAYTIME 07:00 - 23:00 LAeq 16 HOUR & Corresponding LAmax 16 HOUR	54.7	84.0	27.0	37.6	40.5	44.4	49.1	50.5	48.9	43.5	41.3	18.5
NIGHT TIME 23:00 - 07:00 LAeq 8 HOUR & Corresponding LAmax 8 HOUR	44.5	78.3	18.4	29.9	32.4	34.9	39.0	40.8	38.6	32.0	29.9	9.7

7.1.8 Position 2 – 17th – 18th November 2018

NOISE LEVEL SUMMARY ASSESSMENT			Octave Band Centre Frequency (Hz)									
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0k	2.0k	4.0k	8.0k	16.0k
DAYTIME 07:00 - 23:00 LAeq 16 HOUR & Corresponding LAmax 16 HOUR	57.2	81.1	24.4	34.6	36.0	40.8	46.3	50.2	51.5	50.8	49.4	23.8
NIGHT TIME 23:00 - 07:00 LAeq 8 HOUR & Corresponding LAmax 8 HOUR	47.2	73.2	17.4	26.4	25.5	31.7	37.4	41.4	41.7	40.0	38.1	12.8

7.1.9 Position 2 – 18th – 19th November 2018

NOISE LEVEL SUMMARY ASSESSMENT			Octave Band Centre Frequency (Hz)									
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0k	2.0k	4.0k	8.0k	16.0k
DAYTIME 07:00 - 23:00 LAeq 16 HOUR & Corresponding LAmax 16 HOUR	53.1	84.0	25.9	35.2	37.0	41.9	47.4	48.8	47.1	42.4	41.2	17.9
NIGHT TIME 23:00 - 07:00 LAeq 8 HOUR & Corresponding LAmax 8 HOUR	43.0	72.1	16.6	25.2	28.9	32.2	36.4	39.0	37.5	31.4	30.3	9.6

7.1.10 Position 2 – 19th – 20th November 2018

NOISE LEVEL SUMMARY ASSESSMENT			Octave Band Centre Frequency (Hz)									
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0k	2.0k	4.0k	8.0k	16.0k
DAYTIME 07:00 - 23:00 LAeq 16 HOUR & Corresponding LAmax 16 HOUR	54.9	87.6	25.1	35.2	37.5	44.2	47.9	49.6	49.2	46.0	45.4	31.4
NIGHT TIME 23:00 - 07:00 LAeq 8 HOUR & Corresponding LAmax 8 HOUR	0.0	0.0	-7.1	-7.1	-7.1	-7.1	-7.1	-7.1	-7.1	-7.1	-7.1	-7.1

7.1.11 Position 3 – 15th – 16th November 2018

NOISE LEVEL SUMMARY ASSESSMENT			Octave Band Centre Frequency (Hz)									
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0k	2.0k	4.0k	8.0k	16.0k
DAYTIME 07:00 - 23:00 <small>LAeq 16 HOUR & Corresponding LAmax 16 HOUR</small>	53.0	86.0	57.9	54.9	48.7	46.8	48.4	43.7	41.6	49.5	35.6	22.2
NIGHT TIME 23:00 - 07:00 <small>LAeq 8 HOUR & Corresponding LAmax 8 HOUR</small>	42.5	82.3	43.0	42.5	36.9	31.6	30.0	37.2	32.7	38.6	23.4	12.9

7.1.12 Position 3 – 16th – 17th November 2018

NOISE LEVEL SUMMARY ASSESSMENT			Octave Band Centre Frequency (Hz)									
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0k	2.0k	4.0k	8.0k	16.0k
DAYTIME 07:00 - 23:00 <small>LAeq 16 HOUR & Corresponding LAmax 16 HOUR</small>	51.7	82.4	52.1	52.3	46.9	42.2	42.1	44.8	42.8	47.8	36.5	16.7
NIGHT TIME 23:00 - 07:00 <small>LAeq 8 HOUR & Corresponding LAmax 8 HOUR</small>	43.1	74.7	47.3	43.7	38.2	33.9	34.0	36.9	33.5	39.3	25.3	15.6

7.1.13 Position 3 – 17th – 18th November 2018

NOISE LEVEL SUMMARY ASSESSMENT			Octave Band Centre Frequency (Hz)									
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0k	2.0k	4.0k	8.0k	16.0k
DAYTIME 07:00 - 23:00 <small>LAeq 16 HOUR & Corresponding LAmax 16 HOUR</small>	52.6	79.7	55.7	56.7	51.2	48.9	46.5	47.7	43.6	46.5	32.9	17.3
NIGHT TIME 23:00 - 07:00 <small>LAeq 8 HOUR & Corresponding LAmax 8 HOUR</small>	43.7	77.9	50.2	47.1	40.5	37.9	36.6	37.8	33.8	39.2	26.8	15.7

7.1.14 Position 3 – 18th – 19th November 2018

NOISE LEVEL SUMMARY ASSESSMENT			Octave Band Centre Frequency (Hz)									
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0k	2.0k	4.0k	8.0k	16.0k
DAYTIME 07:00 - 23:00 <small>LAeq 16 HOUR & Corresponding LAmax 16 HOUR</small>	51.7	77.6	55.3	55.1	51.7	49.4	46.8	46.4	41.8	45.2	34.8	20.4
NIGHT TIME 23:00 - 07:00 <small>LAeq 8 HOUR & Corresponding LAmax 8 HOUR</small>	44.0	72.2	51.0	48.6	41.3	39.2	38.8	38.8	33.9	38.5	25.2	15.6

7.1.15 Position 3 – 19th – 20th November 2018

NOISE LEVEL SUMMARY ASSESSMENT			Octave Band Centre Frequency (Hz)									
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0k	2.0k	4.0k	8.0k	16.0k
DAYTIME 07:00 - 23:00 <small>LAeq 16 HOUR & Corresponding LAmax 16 HOUR</small>	54.3	80.7	58.6	56.3	54.2	49.5	49.3	48.1	44.6	49.1	36.6	24.1
NIGHT TIME 23:00 - 07:00 <small>LAeq 8 HOUR & Corresponding LAmax 8 HOUR</small>	53.3	74.5	61.0	54.8	50.3	50.0	52.0	41.9	41.4	48.1	35.0	24.2

The following noise levels have been corrected for the highest recorded façade levels and used within the BS 8233: 2014 calculations.

A background noise survey was undertaken from 15th – 20th November 2018 at three positions, front, rear and side of site in order to establish the underlying background noise levels. The maximum day time levels for each position are tabulated below:-

7.1.16 Position 1 – 15th – 20th November 2018

NOISE LEVEL SUMMARY ASSESSMENT			Octave Band Centre Frequency (Hz)									
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0k	2.0k	4.0k	8.0k	16.0k
DAYTIME 07:00 - 23:00 <small>LAeq 16 HOUR & Corresponding LAmax 16 HOUR</small>	54.5	80.3	62.6	59.0	51.1	52.2	51.7	50.4	46.2	39.1	39.6	24.2
NIGHT TIME 23:00 - 07:00 <small>LAeq 8 HOUR & Corresponding LAmax 8 HOUR</small>	46.6	80.6	54.7	49.3	43.1	44.0	43.5	42.8	38.8	31.4	30.5	16.9

7.1.17 Position 2 – 15th – 20th November 2018

NOISE LEVEL SUMMARY ASSESSMENT			Octave Band Centre Frequency (Hz)									
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0k	2.0k	4.0k	8.0k	16.0k
DAYTIME 07:00 - 23:00 <small>LAeq 16 HOUR & Corresponding LAmax 16 HOUR</small>	57.2	81.1	24.4	34.6	36.0	40.8	46.3	50.2	51.5	50.8	49.4	23.8
NIGHT TIME 23:00 - 07:00 <small>LAeq 8 HOUR & Corresponding LAmax 8 HOUR</small>	47.2	73.2	17.4	26.4	25.5	31.7	37.4	41.4	41.7	40.0	38.1	12.8

7.1.18 Position 3 – 15th – 20th November 2018

NOISE LEVEL SUMMARY ASSESSMENT			Octave Band Centre Frequency (Hz)									
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0k	2.0k	4.0k	8.0k	16.0k
DAYTIME 07:00 - 23:00 <small>LAeq 16 HOUR & Corresponding LAmax 16 HOUR</small>	54.3	80.7	58.6	56.3	54.2	49.5	49.3	48.1	44.6	49.1	36.6	24.1
NIGHT TIME 23:00 - 07:00 <small>LAeq 8 HOUR & Corresponding LAmax 8 HOUR</small>	53.3	74.5	61.0	54.8	50.3	50.0	52.0	41.9	41.4	48.1	35.0	24.2

7.1.19 Corrected Noise Levels

The following table demonstrates the resultant noise levels corrected for the worst case scenario of +5 dB correction for the Stubbington Bypass Increase as per the Hampshire County Council Transport Business Case – April 2016 Page 84.

7.1.20 Position 1 – 15th – 20th November 2018

NOISE LEVEL SUMMARY ASSESSMENT			Octave Band Centre Frequency (Hz)									
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0k	2.0k	4.0k	8.0k	16.0k
DAYTIME 07:00 - 23:00 <small>LAeq 16 HOUR & Corresponding LAmax 16 HOUR</small>	59.5	85.3	67.6	64.0	56.1	57.2	56.7	55.4	51.2	44.1	44.6	29.2
NIGHT TIME 23:00 - 07:00 <small>LAeq 8 HOUR & Corresponding LAmax 8 HOUR</small>	51.6	85.6	59.7	54.3	48.1	49.0	48.5	47.8	43.8	36.4	35.5	21.9

7.1.21 Position 2 – 15th – 20th November 2018

NOISE LEVEL SUMMARY ASSESSMENT			Octave Band Centre Frequency (Hz)									
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0k	2.0k	4.0k	8.0k	16.0k
DAYTIME 07:00 - 23:00 <small>LAeq 16 HOUR & Corresponding LAmax 16 HOUR</small>	62.2	86.1	29.4	39.6	41.0	45.8	51.3	55.2	56.5	55.8	54.4	28.8
NIGHT TIME 23:00 - 07:00 <small>LAeq 8 HOUR & Corresponding LAmax 8 HOUR</small>	52.2	78.2	22.4	31.4	30.5	36.7	42.4	46.4	46.7	45	43.1	17.8

7.1.22 Position 3 – 15th – 20th November 2018

NOISE LEVEL SUMMARY ASSESSMENT			Octave Band Centre Frequency (Hz)									
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0k	2.0k	4.0k	8.0k	16.0k
DAYTIME 07:00 - 23:00 <small>LAeq 16 HOUR & Corresponding LAmax 16 HOUR</small>	59.3	85.7	63.6	61.3	59.2	54.5	54.3	53.1	49.6	54.1	41.6	29.1
NIGHT TIME 23:00 - 07:00 <small>LAeq 8 HOUR & Corresponding LAmax 8 HOUR</small>	58.3	79.5	66	59.8	55.3	55	57	46.9	46.4	53.1	40	29.2


8 ProPG PLANNING & NOISE STAGE 1

8.1 Stage 1: Initial Site Noise Risk Assessment

The Stage 1, Initial Noise Risk Assessment, compares the recorded ambient noise levels obtained from the acoustic survey and correlates these against the risk scale within the Pro PG Document in order to evaluate any potential adverse effects the site is currently exposed to with regards to noise.

The outcome of the Stage 1 assessment will determine the level of detail required within Stage 2 in order to demonstrate suitable mitigations can be introduced to ensure continuing compliance with the relevant standards, local planning policies and Pro PG.

The following table demonstrates the Initial Risk Assessment Noise Levels as detailed within ProPG Figure.1:-



Noise Risk Category	0 – Negligible	1 – Low	2 – Medium	3 - High
Average Daytime	<50 dB	50 – 63 dB	63 – 70 dB	>70 dB
Average Night Time	<40 dB	40 – 55 dB	55 – 60 dB	>60 dB
Maximum Night Time			>80 dB (10 Times in 8 Hours)	

Based on the data collected from the aforementioned noise survey, the following ProPG Stage 1 assessments can be made:-

8.2 Potential Façade Noise Levels

8.2.1 Daytime (07:00-23:00)

Time Period	Highest Potential Façade Noise Level	Noise Risk Category
Average Daytime (07:00-23:00)	$L_{Aeq, 16\text{ HOUR}}$ 62 dB	1 – Low

8.2.2 Night Time (23:00-07:00)

Time Period	Highest Potential Façade Noise Level	Noise Risk Category
Average Night Time (23:00-07:00)	$L_{Aeq, 16\text{ HOUR}}$ 58 dB Maximum (10 Times) – L_{Amax} 79.2 dB	2 – Medium 55 – 60 dB >80 dB (10 Times in 8 Hours)

8.3 Risk Assessment

8.3.1 Daytime (07:00-23:00)

Risk Assessment Category	Risk Assessment
1 – Low	At low noise levels, the site is likely to be acceptable from a noise perspective provided that a good acoustic design process is followed and is demonstrated in an ADS which confirms how the adverse impacts of noise will be mitigated and minimised in the finished development.


8.3.2 Night Time (23:00-07:00)

Risk Assessment Category	Risk Assessment
2 – Medium	As noise levels increase, the site is likely to be less suitable from a noise perspective and any subsequent application may be refused unless a good acoustic design process is followed and is demonstrated in an ADS which confirms how the adverse impacts of noise will be mitigated and minimised, and which clearly demonstrate that a significant adverse noise impact will be avoided in the finished development.

The above table demonstrates this site is located within Noise Risk Category 1 which suggests a low level of risk for daytime levels and Noise Risk Category 2 which suggests a Medium level of risk for night time levels. Therefore, further mitigation levels will be required at Stage 2.

9 ProPG PLANNING & NOISE STAGE 2 - ELEMENT 1 – GOOD ACOUSTIC DESIGN

Given the size and orientation of the proposed site, it is recommended that the developer adopt, where practically possible, a good acoustic design which should include careful consideration of the positioning of the proposed properties together with thoughts being taken as to internal layouts to minimise noise sensitive rooms facing onto dominant noise sources within the local areas.



PROPOSED SITE LAYOUT

10 ELEMENT 2 – INTERNAL NOISE LEVEL GUIDELINES

10.1 Discussion of Results

It can be seen from the attached graph and downloaded results that the external noise levels have followed the expected path and remained fairly constant throughout the day. The levels then gradually dropped off as the evening progressed and began to rise when morning traffic levels increased. Calculations 10.4 & 10.5 include the +5 dB increase.

10.2 Existing Noise Levels – Daytime (07:00 – 23:00)




Daytime prior to development

10.3 Existing Noise Levels – Night Time (23:00 – 07:00)




Night time prior to development

10.4 Proposed Noise levels – Daytime (07:00 – 23:00)



10.5 Proposed Noise levels – Night Time (23:00 – 07:00)



10.6 Recommendations

For the purpose of this assessment, the corresponding façade levels will be used within the BS 8233: 2014 calculations in order evaluate the worst case scenario and select the correct window specification.

Therefore, in order to achieve the required noise levels of $L_{Aeq\ 16\ HOUR}$ 35 dB for habitable rooms daytime and $L_{Aeq\ 8\ HOUR}$ 30 dB for Bedroom at night within the proposed, the following additional acoustic measures have been calculated.

It should be noted that the calculations have been made with the proposed windows closed. Additional calculations were made for the top floor due to the influence of sound transmission into the various rooms via the roof / ceiling i.e. an increased impeding façade. Inputted levels into the calculation sheets have been corrected for distance attenuation and free field in accordance with the aforementioned British Standard.

10.7 Calculation Procedure to BS 8233: 2014

The following calculations have been carried out in order to determine the required window and ventilation specification in order to meet the requirements of BS 8233: 2014.

10.8 Ground Floor Lounge

Proposed Window Configuration		4 / 16 / 4 with Standard through frame slot vent									
Leqff	<i>The equivalent continuous sound pressure level outside the room elements under consideration</i>										
A0	<i>The reference absorption area of 10m² and is independent of frequency</i>										
Sf	<i>The total façade area of the room in question</i>										
Swi	<i>The area of the windows in the room</i>										
Sew	<i>The area of the external wall of the room</i>										
Srr	<i>The area of the ceiling of the room (if applicable)</i>										
S	<i>The total area of the elements through which sound enters the room</i>										
Dne	<i>The insulation value of the trickle ventilator (if applicable)</i>										
Rwi	<i>The sound reduction index of the window</i>										
Rew	<i>The sound reduction index of the external wall</i>										
Rrr	<i>The sound reduction index of the ceiling/roof (if applicable)</i>										
A	<i>The equivalent absorption area of the receiving room where A=0.163V/T</i>										
Formula	$Leq2 = Leqff + 10\log[A0/S * 10^{(-Dne/10)} + Swi/S * 10^{(-Rwi/10)} + Sew/10^{10^{(-Rew/10)}} + Srr/S * 10^{(-Rrr/10)}] + 10\log(S/A) + 3$										
Octave Band Centre Frequency (Hz)											
	125	250	500	1000	2000	4000					
Sf	10	10	10	10	10	10					
Sr	0	0	0	0	0	0					
Swi	2	2	2	2	2	2					
Sew	8	8	8	8	8	8					
Srr	0	0	0	0	0	0					
S	10	10	10	10	10	10					
A0	10	10	10	10	10	10					
V	29	29	29	29	29	29					
T (BS8233)	0.50	0.50	0.50	0.50	0.50	0.50					
A	9.3	9.3	9.3	9.3	9.3	9.3					
Daytime Leqff	54.1	55.2	54.7	53.4	49.2	42.1					
Night time Leqff	53.3	53.0	55.0	44.9	44.4	51.1					
Dne	33.0	32.0	29.0	29.0	31.0	33.0					
Rwi	21.1	19.7	31.1	38.2	41.3	38.7					
Rew	40.0	44.0	45.0	51.0	56.0	56.0					
Rrr	28.0	34.0	40.0	45.0	49.0	49.0					
Predicted dB(A) Level Within The Above Room During Daytime Hours (07:00-23:00)			L_{Aeq 16 HOUR}	31.9	dB(A)						
Predicted dB(A) Level Within The Above Room During Night Time Hours (23:00-07:00)			L_{Aeq 8 HOUR}	30.0	dB(A)						

10.9 Top Floor Bedroom

Proposed Window Configuration		4 / 16 / 4 with Standard through frame slot vent									
Leqff	<i>The equivalent continuous sound pressure level outside the room elements under consideration</i>										
A0	<i>The reference absorption area of 10m² and is independent of frequency</i>										
Sf	<i>The total façade area of the room in question</i>										
Swi	<i>The area of the windows in the room</i>										
Sew	<i>The area of the external wall of the room</i>										
Srr	<i>The area of the ceiling of the room (if applicable)</i>										
S	<i>The total area of the elements through which sound enters the room</i>										
Dne	<i>The insulation value of the trickle ventilator (if applicable)</i>										
Rwi	<i>The sound reduction index of the window</i>										
Rew	<i>The sound reduction index of the external wall</i>										
Rrr	<i>The sound reduction index of the ceiling/roof (if applicable)</i>										
A	<i>The equivalent absorption area of the receiving room where A=0.163V/T</i>										
Formula	$\text{Leq2} = \text{Leqff} + 10\log[A0/S*10^{(-Dne/10)} + Swi/S*10^{(-Rwi/10)} + Sew/10*10^{(-Rew/10)} + Srr/S*10^{(-Rrr/10)}] + 10\log(S/A) + 3$										
	Octave Band Centre Frequency (Hz)										
	125	250	500	1000	2000	4000					
Sf	7	7	7	7	7	7					
Sr	12	12	12	12	12	12					
Swi	1.6	1.6	1.6	1.6	1.6	1.6					
Sew	5.4	5.4	5.4	5.4	5.4	5.4					
Srr	12	12	12	12	12	12					
S	19	19	19	19	19	19					
A0	10	10	10	10	10	10					
V	25	25	25	25	25	25					
T (BS8233)	0.50	0.50	0.50	0.50	0.50	0.50					
A	8.0	8.0	8.0	8.0	8.0	8.0					
Daytime Leqff	53.1	54.2	53.7	52.4	48.2	41.1					
Night time Leqff	52.3	52.0	54.0	43.9	43.4	50.1					
Dne	33.0	32.0	29.0	29.0	31.0	33.0					
Rwi	21.1	19.7	31.1	38.2	41.3	38.7					
Rew	40.0	44.0	45.0	51.0	56.0	56.0					
Rrr	28.0	34.0	40.0	45.0	49.0	49.0					
Predicted dB(A) Level Within The Above Room During Daytime Hours (07:00-23:00)	L_{Aeq 16 HOUR}		31.7		dB(A)						
Predicted dB(A) Level Within The Above Room During Night Time Hours (23:00-07:00)	L_{Aeq 8 HOUR}		29.9		dB(A)						

10.10 Ventilation (D_{ne})

Octave Band Frequency	125	250	500	1000	2000	4000	$D_{n,e,w}$
Standard through frame slot vent	33.0	32.0	29.0	29.0	31.0	33.0	30.5

10.11 Glazing (R_{wi})

Octave Band Frequency	125	250	500	1000	2000	4000	R_w
4mm glass / 16mm air gap / 4mm glass	21.1	19.7	31.1	38.2	41.3	38.7	35

10.12 Walls (R_{ew})

Octave Band Frequency	125	250	500	1000	2000	4000	R_w
Brick and Concrete Block	40.0	44.0	45.0	51.0	56.0	56.0	50

10.13 Roof (R_{rr})

Octave Band Frequency	125	250	500	1000	2000	4000	R_w
Minimum Value	28.0	34.0	40.0	45.0	49.0	49.0	43

The above are minimum construction attenuation values and should alternative methods be selected; these should be equal to or greater than the above corresponding values. Calculations carried out have indicated the following specifications should be installed for this site.

10.14 Glazing & Ventilation Assessment

Dwellings on the proposed development will require a standard 4mm glass / 16mm air gap / 4mm glass double glazed windows and a standard trickle vents.

The above should be implemented to all rooms to ensure the internal noise levels are acceptable in terms of the assessment to British Standard 8233: 2014. This also takes into account the corrected values for the proposed Stubbington Bypass.

10.15 Night Noise Guidelines Europe 2009

The Night Noise Guidelines 2009 make direct reference to the World Health Organisations Guidelines for Community Noise 1999 with recommended guideline criteria of L_{Aeq} 30 dB indoors for continuous noise. The document goes on to explain that sleep disturbance correlates best with L_{Amax} and effects have been observed at 45 dB or less. This is particularly true if the background noise level is low. Noise events exceeding 45 dB(A) should therefore be limited.

Pro PG: Planning and Noise Appendix A 'Dealing with Noise Events' A.17 states that:-

Various studies have linked the L_{Amax} from individual noise events to behavioural awakenings. For example one study found that the "Probability of sleep stage changes to wake/S1 from railway noise increased significantly from 6.5% at 35 dB(A) to 20.5% at 80 dB(A) $L_{Amax,F}$ whilst another study concluded that "noise disturbance of sleep may be expected to become significant once the outdoor L_{Aeq} exceeds 55 dB provided peak noise levels do not exceed 75 to 80 dB. Higher L_{Aeq} values up to 60 dB may be allowed providing the peak levels do not exceed 85 dB, and the number of such events is less than about 20 per night". Based on these studies it can be concluded that at night (2300 - 0700 hrs) a significant effect on sleep disturbance e.g. behavioural awakening, is likely to occur where the maximum sound level at the façade of a building with partially open windows is above:

85 dB $L_{Amax,F}$ (where the number of events exceeding this value is ≤ 20);

or

80 dB $L_{Amax,F}$ (where the number of events exceeding this value is > 20).

Pro PG: Planning and Noise Appendix A 'Dealing with Noise Events' A.18 goes on to explain that:-

A.18 The main body of sleep research is consistent with a careful interpretation of the viewpoint set out in the World Health Organisation Guidelines which for the ordinary population is that:

- ✓ *Impacts on sleep can be detected from relatively low level maximum noise events, however the degree of resulting harm may not be significant.*
- ✓ *'Effects' on sleep (such as EEG awakenings and sleep stage changes) occur spontaneously in the general population many times per night regardless of any impacts due to noise.*
- ✓ *The smaller the number of noise events, the louder the maximum noise level that can be tolerated without adverse effects upon sleep; subject to an upper limit.*
- ✓ *At relatively low levels e.g. around 45 dB $L_{Amax,F}$ when sufficient number of such events take place during the night the adverse effects of individual noise events are likely to be limited to sleep disturbance in the form of changes in sleep state or perhaps some EEG awakenings.*
- ✓ *It normally requires noise levels higher than 45 dB $L_{Amax,F}$ before significant adverse effects such as behavioural awakenings, difficulty getting to sleep, premature awakening or difficulty getting back to sleep generally occur and the latest field research on and aircraft noise suggest that it requires internal L_{Amax} noise levels of around 65 dB before noise induced awakenings become distinguishable from spontaneous awakenings).*

Therefore the following tabulated results from the worst night have been calculated and demonstrate compliance with the requirements of Pro PG.

NIGHT TIME NOISE LEVELS 23:00 - 07:00 15 MINUTE SAMPLES				
Date / Time	LAeq	LMax	L _{Amax,F} 80 - 85 dB	L _{Amax,F} > 85 dB
23:00 - 23:15	54.0	81.5	81.5	
23:15 - 23:30	44.0	71.1		
23:30 - 23:45	41.3	58.3		
23:45 - 00:00	41.6	56.4		
00:00 - 00:15	40.2	47.8		
00:15 - 00:30	41.4	48.8		
00:30 - 00:45	41.3	49.4		
00:45 - 01:00	41.1	49.6		
01:00 - 01:15	41.2	50.5		
01:15 - 01:30	41.3	49.9		
01:30 - 01:45	44.2	59.3		
01:45 - 02:00	40.7	50.5		
02:00 - 02:15	40.5	49.8		
02:15 - 02:30	40.4	48.3		
02:30 - 02:45	40.4	48.7		
02:45 - 03:00	40.4	47.8		
03:00 - 03:15	40.0	51.5		
03:15 - 03:30	40.0	51.9		
03:30 - 03:45	40.8	55.1		
03:45 - 04:00	41.0	57.6		
04:00 - 04:15	40.6	54.2		
04:15 - 04:30	40.6	60.3		
04:30 - 04:45	41.4	62.1		
04:45 - 05:00	41.5	56.0		
05:00 - 05:15	43.8	59.9		
05:15 - 05:30	39.6	55.2		
05:30 - 05:45	40.2	58.2		
05:45 - 06:00	40.4	56.6		
06:00 - 06:15	50.4	69.1		
06:15 - 06:30	53.3	61.1		
06:30 - 06:45	53.5	68.3		
06:45 - 07:00	53.9	69.3		
Total Event Count			1	0
Pro PG Annex Event Quantity Criteria			>20	<20
Pro PG Criteria Assessment			Achieved	Achieved

11 ELEMENT 3 – EXTERNAL AMENITY AREA NOISE ASSESSMENT

11.1 Outdoor Living Areas

The World Health Organisation ‘Guidelines for Community Noise’ gives guidance as to desirable noise levels that should be achieved within outdoor living areas such as gardens, patios and verandas etc.

Table 1: Guideline values for community noise in specific environments, details the desirable target noise levels within various areas.

Outdoor Living Area	
Serious Annoyance, daytime and evening	$L_{Aeq\ 16\ HOUR}$ 55 dB
Moderate Annoyance, daytime and evening	$L_{Aeq\ 16\ HOUR}$ 50 dB

In order to evaluate the external noise levels within the proposed development, and to correctly and accurately select the precise required minimum screen heights, the 3D modelling software CADNA A is to be used. Initially, the site plan is to be overlaid onto Google Earth and then imported directly into CADNA A using the geometric co-ordinates.

From this, the monitoring positions and noise sources such as roads are added. The output noise levels from the roads are then increased until the monitored noise levels are achieved at the monitoring position. This model is then saved and used as a working 3D acoustic model of the site.


The proposed buildings are then constructed on a 3D bases and receptors placed within the garden areas.

The calculation software is then run to evaluate the garden levels within sample plots across the development.

The following CADNA A screen shots demonstrate the existing sites working 3D model. The levels at the measurement position correlate with the measured daytime average levels detailed on page 20 of this report.



The development has external living areas on the development and therefore this criteria / guideline would be appropriately considered within the proposed rear residential garden areas.



The guideline has been considered acceptable criteria for this assessment given the sites geographical location and proximity to a potential major trunk road (New Stubbington Bypass). The layout has been designed in order to allow for acoustics and minimise the noise levels within the outdoor living spaces. The above calculation demonstrates the external living spaces surrounding the houses are likely to see noise levels below the lower guideline of 50 dB.

12 ELEMENT 4 – ASSESSMENT OF OTHER RELEVANT ISSUES

The National Planning Policy Framework 2019 (NPPF) and assessments to the Noise Policy Statement for England 2010 (NPSE) should be made in conjunction with each other. Paragraphs 180 - 183 of the National Planning Policy Framework 2019 (NPPF) states the following:

Paragraph 180 Planning policies and decisions should also ensure that new development is appropriate for its location taking into account the likely effects (including cumulative effects) of pollution on health, living conditions and the natural environment, as well as the potential sensitivity of the site or the wider area to impacts that could arise from the development. In doing so they should:

- a) Mitigate and reduce to a minimum potential adverse impacts resulting from noise from new development – and avoid noise giving rise to significant adverse impacts on health and the quality of life.
- b) Identify and protect tranquil areas which have remained relatively undisturbed by noise and are prized for their recreational and amenity value for this reason.

Paragraph 181 Planning policies and decisions should sustain and contribute towards compliance with relevant limit values or national objectives for pollutants. So far as possible these opportunities should be considered at the plan-making stage, to ensure a strategic approach and limit the need for issues to be reconsidered when determining individual applications.

Paragraph 182 Planning policies and decisions should ensure that new development can be integrated effectively with existing businesses and community facilities (such as places of worship, pubs, music venues and sports clubs). Existing businesses and facilities should not have unreasonable restrictions placed on them as a result of development permitted after they were established. Where the operation of an existing business or community facility could have a significant adverse effect on new development (including changes of use) in its vicinity, the applicant (or ‘agent of change’) should be required to provide suitable mitigation before the development has been completed.

Paragraph 183 The focus of planning policies and decisions should be on whether proposed development is an acceptable use of land, rather than the control of processes or emissions (where these are subject to separate pollution control regimes). Planning decisions should assume that these regimes will operate effectively. Equally, where a planning decision has been made on a particular development, the planning issues should not be revisited through the permitting regimes operated by pollution control authorities

The Noise Policy Statement for England gives various levels of effect as detailed within this report.

With the glazing / ventilation specifications achieved within this report, the development can be implemented within the guidelines of the aforementioned documents and ensure a conclusion of **NOEL – No Observed Effect Level**. This is the level below which no effect can be detected. In simple terms, below this level, there is no detectable effect on health and quality of life due to the noise.

13 ACOUSTIC DESIGN STATEMENT

Good Acoustic Design	Given the size and orientation of the proposed site, it is recommended that the developer adopted, where practically possible, a good acoustic design which should include careful consideration of the positioning of the proposed properties together with thoughts being taken as to internal layouts to minimise noise sensitive rooms facing onto dominant noise sources within the local areas.
Internal Noise Levels	Calculations have been carried out and assessments made to BS 8233: 2014 together with design specifications supplied for the required glazing and ventilation specifications required across the development to ensure compliance.
LAmax dB Noise Levels	Assessments and calculations demonstrate that the LAmax dB Levels are within the criteria set out within PRoPG
External Living Areas	The guideline has been considered acceptable criteria for this assessment given the sites geographical location and proximity to a potential major trunk road (New Stubbington Bypass). The layout has been designed in order to allow for acoustics and minimise the noise levels within the outdoor living spaces. The above calculation demonstrates the external living spaces surrounding the houses are likely to see noise levels below the lower guideline of 50 dB.
NPPF & NPSE	With the glazing / ventilation specifications achieved within this report, the development can be implemented within the guidelines of the aforementioned documents and ensure a conclusion of NOEL – No Observed Effect Level . This is the level below which no effect can be detected. In simple terms, below this level, there is no detectable effect on health and quality of life due to the noise.
OVERALL OUTCOME	NOEL – No Observed Effect Level

14 RECOMMENDATION TO DECISION MAKER

Levels have been recorded and assessments made in accordance with the relevant standards. Internal criteria's have been set and calculations made in order to determine the minimum construction details required in order to meet the desired level within the proposed residential dwellings and satisfy the local council's requirements.

National Planning Policy Framework 2019 suggests that planning permission should be granted unless any adverse impacts of doing so would significantly and demonstrably outweigh the benefits, when assessed against the policies in the framework taken as a whole, or specific policies in the framework indicate the application should be restricted.

Based on the calculations and assessments made within this report it is the professional opinion of Sound Advice Acoustics Ltd that the proposed development can demonstrate compliance with the National Planning Policy Framework 2018, NPPF & NPSE and that, with regards to sound, planning permission can be granted using the following parameters.

As indicated in Section 2 of ProPG, following the ProPG approach will lead to the choice of one of four possible recommendations from the noise practitioner to the decision maker:

- A. Planning consent may be granted without any need for noise conditions;
- B. Planning consent may be granted subject to the inclusion of suitable noise conditions;
- C. Planning consent should be refused on noise grounds in order to avoid significant adverse effects ("avoid");
or
- D. Planning consent should be refused on noise grounds in order to prevent unacceptable adverse effects ("prevent").

RECOMMENDATION TO DECISION MAKER

Grant with Noise Conditions

15 CONCLUSION

15.1 Background Noise Levels

A background noise survey was undertaken from 15th – 20th November 2018 at three positions, front, rear and side of site in order to establish the underlying background noise levels. The maximum day time levels for each position are tabulated below:-

Assessment Position	Date Start	Date Finish	Daytime LAeq	Night Time LAeq
Position 1 Front	15/11/2018	20/11/2018	54.3	46.6
Position 2 Side	15/11/2018	20/11/2018	57.2	47.2
Position 3 Rear	15/11/2018	20/11/2018	54.3	53.3

15.1.1 Corrected Noise Levels

The following table demonstrates the resultant noise levels corrected for the worst case scenario of +5 dB correction for the Stubbington Bypass Increase as per the Hampshire County Council Transport Business Case – April 2016 Page 84.

Assessment Position	Date Start	Date Finish	Daytime LAeq	Night Time LAeq
Position 1 Front	15/11/2018	20/11/2018	59.3	51.6
Position 2 Side	15/11/2018	20/11/2018	62.2	52.2
Position 3 Rear	15/11/2018	20/11/2018	59.3	58.3

15.2 Potential Façade Noise Levels

15.2.1 Daytime (07:00-23:00)

Time Period	Highest Potential Façade Noise Level	Noise Risk Category
Average Daytime (07:00-23:00)	L _{Aeq, 16 HOUR} 62 dB	1 – Low

15.2.2 Night Time (23:00-07:00)

Time Period	Highest Potential Façade Noise Level	Noise Risk Category
Average Night Time (23:00-07:00)	L _{Aeq, 16 HOUR} 58 dB Maximum (10 Times) – L _{Max} 78.6 dB	2 – Medium 55 – 60 dB >80 dB (10 Times in 8 Hours)

15.3 Risk Assessment

15.3.1 Daytime (07:00-23:00)

Risk Assessment Category	Risk Assessment
1 – Low	At low noise levels, the site is likely to be acceptable from a noise perspective provided that a good acoustic design process is followed and is demonstrated in an ADS which confirms how the adverse impacts of noise will be mitigated and minimised in the finished development.

15.3.2 Night Time (23:00-07:00)

Risk Assessment Category	Risk Assessment
2 – Medium	As noise levels increase, the site is likely to be less suitable from a noise perspective and any subsequent application may be refused unless a good acoustic design process is followed and is demonstrated in an ADS which confirms how the adverse impacts of noise will be mitigated and minimised, and which clearly demonstrate that a significant adverse noise impact will be avoided in the finished development.

The above table demonstrates this site is located within Noise Risk Category 1 which suggests a low level of risk for daytime levels and Noise Risk Category 2 which suggests a Medium level of risk for night time levels. Therefore, further mitigation levels will be required at Stage 2.

15.4 CONCLUSION

Dwellings on the proposed development will require a standard 4mm glass / 16mm air gap / 4mm glass double glazed windows and a standard trickle vents.

The above should be implemented to all rooms to ensure the internal noise levels are acceptable in terms of the assessment to British Standard 8233: 2014. This also takes into account the corrected values for the proposed Stubbington Bypass.

The guideline has been considered acceptable criteria for this assessment given the sites geographical location and proximity to a potential major trunk road (New Stubbington Bypass). The layout has been designed in order to allow for acoustics and minimise the noise levels within the outdoor living spaces. The calculation demonstrates the external living spaces surrounding the houses are likely to see noise levels below the lower guideline of 50 dB.

Levels have been recorded and assessments made in accordance with the relevant standards. Internal criteria's have been set and calculations made in order to determine the minimum construction details required in order to meet the desired level within the proposed residential dwellings and satisfy the local council's requirements.

National Planning Policy Framework 2019 suggests that planning permission should be granted unless any adverse impacts of doing so would significantly and demonstrably outweigh the benefits, when assessed against the policies in the framework taken as a whole, or specific policies in the framework indicate the application should be restricted.

Based on the calculations and assessments made within this report it is the professional opinion of Sound Advice Acoustics Ltd that the proposed development can demonstrate compliance with the National Planning Policy Framework 2018, NPPF & NPSE and that, with regards to sound, planning permission can be granted.

16 UNCERTAINTY

In line with the requirements of section 10 of British Standard 4142: 2014 it is expected that the reported expanded uncertainty with a confidence limit of 95% and assuming a convergence of k=2 is likely to be +/- 2.1dB. Uncertainty, in this instance has been minimised by undertaking longer background noise measurements over a 96-hour period.


16.1 Uncertainty Budget

Sources of Uncertainty	Uncertainty Notes	Commentary	Value (half Width)	Convert to Same Units (dB)	Distribution Divisor			Standard Uncertainty (u) dB
					Normal	Rectangular	Other	
Measurement Position	Choice of position,,	1m in 20m		0.2		rect(v/3)		0.13
	microphone orientation	Type 1 0 - 30deg	0.4		Normal			0.50
Instrumentation	Calibration	Calibration Drift	0.1		Normal			0.10
	Accuracy and precision (type 1)	Type 1 practical	1.9			rect(v/3)		0.50
Background Noise Level	Timing of Measurement							
Background Noise Level	Modal Analysis Day	Calculated Standard Deviation	3.7				s/vn	0.39
Background Noise Level	Modal Analysis Night	Calculated Standard Deviation	2.2				s/vn	0.16
Combined Uncertainty (root sum of squares)								1.05
Expanded Uncertainty U = Kuc (95% Confidence K =2)								2.1
Final Answer Expressed as Value +/- U dB with a confidence Level of 95%								
REFERENCE: Uncertainty Budget Calculated in line with M3003: The Expression of Uncertainty and Confidence in Measurement Edition 3, November 2012 and A Good Practice Guide on the Sources and Magnitude of Uncertainty Arising in the Practical Measurement of Environmental Noise N J Craven, G Kerry Edition 1a – May 2007.								

17 RESULTS


17.1 15th – 16th November 2018 Position 1

NOISE LEVEL SUMMARY ASSESSMENT				Octave Band Centre Frequency (Hz)									
Date / Time	LAeq	LAmx	31.5	63	125	250	500	1.0k	2.0k	4.0k	8.0k	16.0k	
DAYTIME 07:00 - 23:00 LAeq 16 HOUR & Corresponding LAmx 16 HOUR	53.9	79.9	58.6	56.9	51.5	51.8	51.1	49.7	45.5	39.4	39.3	22.1	
NIGHT TIME 23:00 - 07:00 LAeq 8 HOUR & Corresponding LAmx 8 HOUR	46.4	81.5	49.3	47.7	41.1	41.3	43.3	41.7	39.4	34.6	32.9	18.3	
DAYTIME NOISE LEVELS 07:00 - 23:00 1 HOUR SAMPLES													
Date / Time	LAeq	LAmx	31.5	63	125	250	500	1.0 k	2.0 k	4.0 k	8.0 k	16.0 k	
07:00 - 08:00	56.2	77.4	60.2	57.1	51.6	52.2	53.8	52.3	47.6	37.9	39.8	17.6	
08:00 - 09:00	55.8	74.6	62.9	59.1	53.4	53.8	52.2	51.7	47.7	39.2	41.5	21.7	
09:00 - 10:00	55.7	70.3	61.5	59.4	57.7	54.8	53.0	51.0	47.1	37.2	37.4	17.2	
10:00 - 11:00	55.6	73.7	60.2	60.2	52.1	54.3	52.1	51.1	47.1	42.4	42.6	24.0	
11:00 - 12:00	55.2	72.5	60.7	58.8	50.5	53.3	51.8	50.9	47.3	40.1	41.8	24.8	
12:00 - 13:00	55.6	75.1	59.3	57.3	52.1	54.1	52.6	51.3	47.2	39.6	38.8	21.0	
13:00 - 14:00	55.2	75.3	57.3	55.7	48.9	53.3	51.7	50.8	47.1	40.7	42.5	26.3	
14:00 - 15:00	56.5	78.8	60.3	58.9	51.1	53.2	54.7	52.4	47.2	39.8	40.4	23.4	
15:00 - 16:00	54.8	75.6	57.8	57.7	53.3	53.4	50.9	50.2	47.4	41.4	41.0	25.9	
16:00 - 17:00	53.3	77.2	57.8	55.4	50.8	50.7	49.1	48.4	45.1	43.2	40.5	22.1	
17:00 - 18:00	47.7	73.8	55.2	54.1	49.4	46.6	43.6	41.9	40.1	38.0	33.4	19.4	
18:00 - 19:00	50.5	79.9	54.6	53.9	48.0	45.3	49.4	46.7	39.0	36.0	32.2	17.9	
19:00 - 20:00	45.0	67.3	51.3	51.0	46.6	43.1	41.6	39.2	36.8	35.4	31.2	17.3	
20:00 - 21:00	48.7	74.5	50.5	50.8	44.0	41.3	48.8	43.7	37.4	35.6	32.1	18.1	
21:00 - 22:00	47.9	79.3	50.1	51.0	44.7	41.0	42.7	46.4	37.0	35.1	31.6	17.7	
22:00 - 23:00	43.4	67.3	47.6	48.1	39.1	34.8	38.7	38.0	36.2	34.8	31.0	17.3	
NIGHT TIME NOISE LEVELS 23:00 - 07:00 15 MINUTE SAMPLES													
Date / Time	LAeq	LAmx	31.5	63	125	250	500	1.0 k	2.0 k	4.0 k	8.0 k	16.0 k	
23:00 - 23:15	54.0	81.5	44.6	44.2	38.0	38.1	55.6	48.5	38.7	34.6	31.1	17.3	
23:15 - 23:30	44.0	71.1	49.0	50.0	44.3	41.8	38.9	39.8	36.0	34.3	30.5	16.8	
23:30 - 23:45	41.3	58.3	44.9	43.6	33.3	32.6	32.5	35.1	35.6	34.1	30.4	16.7	
23:45 - 00:00	41.6	56.4	48.1	47.5	36.9	32.8	33.2	36.4	35.4	33.8	30.2	16.5	
00:00 - 00:15	40.2	47.8	43.8	42.1	30.5	28.9	29.1	33.2	34.9	33.5	30.1	16.5	
00:15 - 00:30	41.4	48.8	43.3	41.2	30.8	29.0	34.5	34.5	35.3	34.6	30.9	17.3	
00:30 - 00:45	41.3	49.4	43.3	41.5	30.8	30.2	34.0	34.4	35.3	34.6	30.6	17.1	
00:45 - 01:00	41.1	49.6	42.5	38.9	30.2	29.0	34.0	34.1	35.1	34.4	30.5	16.9	
01:00 - 01:15	41.2	50.5	42.9	39.9	30.5	28.8	34.1	34.2	35.1	34.6	30.6	17.0	
01:15 - 01:30	41.3	49.9	43.6	40.3	30.3	29.1	34.1	34.4	35.0	34.6	30.8	17.2	
01:30 - 01:45	44.2	59.3	48.7	56.5	46.2	39.8	40.8	37.7	36.3	35.0	30.8	17.3	
01:45 - 02:00	40.7	50.5	44.6	40.8	30.6	29.4	33.2	34.1	34.5	33.8	30.2	16.9	
02:00 - 02:15	40.5	49.8	44.9	41.1	30.7	29.6	33.0	33.9	34.2	33.6	30.1	16.7	
02:15 - 02:30	40.4	48.3	45.8	41.3	30.9	29.6	33.2	33.8	34.2	33.6	30.0	16.8	
02:30 - 02:45	40.4	48.7	46.2	42.0	31.1	29.7	32.9	33.8	34.1	33.6	30.1	16.8	
02:45 - 03:00	40.4	47.8	46.4	42.1	35.1	30.8	33.3	33.9	34.0	33.5	30.1	16.7	
03:00 - 03:15	40.0	51.5	46.4	41.7	30.7	28.4	31.8	33.5	33.9	33.3	30.1	16.8	
03:15 - 03:30	40.0	51.9	47.4	46.6	30.8	27.8	28.7	33.4	34.1	33.4	30.7	17.4	
03:30 - 03:45	40.8	55.1	45.6	40.8	30.5	28.0	31.8	33.8	34.6	34.4	32.0	18.4	
03:45 - 04:00	41.0	57.6	45.3	40.8	30.6	28.2	31.7	33.8	34.6	34.7	32.7	19.0	
04:00 - 04:15	40.6	54.2	46.3	41.4	30.6	28.0	29.9	33.3	34.5	34.5	32.6	19.0	
04:15 - 04:30	40.6	60.3	45.6	41.8	31.6	29.3	30.2	33.4	34.6	34.4	32.3	18.7	
04:30 - 04:45	41.4	62.1	45.4	41.3	31.3	28.5	30.7	33.8	35.1	35.5	33.6	20.0	
04:45 - 05:00	41.5	56.0	50.0	48.1	42.4	39.7	33.7	33.7	34.9	34.7	32.3	18.6	
05:00 - 05:15	43.8	59.9	51.7	49.3	45.5	43.7	40.3	38.1	34.8	33.8	30.9	17.3	
05:15 - 05:30	39.6	55.2	45.9	41.0	30.8	27.8	27.9	32.1	33.9	33.4	30.5	17.0	
05:30 - 05:45	40.2	58.2	46.3	43.3	30.9	29.0	28.7	33.2	34.6	33.7	31.1	17.5	
05:45 - 06:00	40.4	56.6	47.5	44.9	32.0	29.9	29.1	33.5	34.6	33.9	31.4	18.1	
06:00 - 06:15	50.4	69.1	53.3	54.4	52.1	50.5	46.9	45.9	42.3	34.6	31.7	17.8	
06:15 - 06:30	53.3	61.1	54.6	52.3	44.3	48.7	47.8	49.5	47.4	35.8	32.8	18.4	
06:30 - 06:45	53.5	68.3	56.4	50.8	44.1	49.1	48.6	49.5	47.5	37.0	35.0	19.6	
06:45 - 07:00	53.9	69.3	57.1	52.2	44.2	48.8	48.1	49.7	47.6	38.4	42.9	25.3	



17.2 16th – 17th November 2018 Position 1

NOISE LEVEL SUMMARY ASSESSMENT				Octave Band Centre Frequency (Hz)									
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0k	2.0k	4.0k	8.0k	16.0k	
DAYTIME 07:00 - 23:00 LAeq 16 HOUR & Corresponding LAmax 16 HOUR	54.2	83.7	57.5	56.1	52.4	50.8	50.9	49.3	46.4	42.7	43.0	26.9	
NIGHTTIME 23:00 - 07:00 LAeq 8 HOUR & Corresponding LAmax 8 HOUR	40.6	70.3	49.6	47.5	42.7	39.6	36.4	34.3	31.7	31.7	31.0	15.7	
DAYTIME NOISE LEVELS 07:00 - 23:00 1 HOUR SAMPLES													
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0 k	2.0 k	4.0 k	8.0 k	16.0 k	
07:00 - 08:00	55.2	70.6	60.8	56.1	52.5	52.3	50.5	50.4	47.9	44.4	44.0	22.5	
08:00 - 09:00	54.6	69.1	57.2	55.9	51.2	52.1	49.8	49.9	47.5	42.8	41.9	20.7	
09:00 - 10:00	55.5	72.5	58.5	57.1	51.3	52.1	51.1	50.3	47.9	44.2	46.5	24.6	
10:00 - 11:00	56.2	70.3	60.5	58.5	51.7	51.8	52.7	50.8	48.5	46.5	45.9	30.2	
11:00 - 12:00	56.6	75.7	60.9	59.5	53.6	52.5	53.5	51.3	48.9	45.3	45.1	29.8	
12:00 - 13:00	55.9	73.5	56.0	54.6	50.4	51.3	52.4	50.6	48.2	44.9	46.2	31.5	
13:00 - 14:00	56.3	69.5	57.8	56.8	53.4	53.5	51.9	50.8	48.8	45.8	46.9	32.3	
14:00 - 15:00	55.2	72.9	58.3	55.8	50.2	51.5	51.6	50.1	48.1	42.7	42.9	27.6	
15:00 - 16:00	54.6	72.8	57.4	56.4	50.4	51.4	50.5	50.0	47.8	40.4	39.1	18.4	
16:00 - 17:00	55.1	72.7	55.6	54.7	49.3	49.9	51.7	49.8	47.5	44.3	44.9	30.1	
17:00 - 18:00	48.0	73.7	55.1	54.7	49.9	47.2	45.0	42.6	39.1	36.3	33.1	18.8	
18:00 - 19:00	53.0	79.2	53.2	51.4	46.5	47.0	53.7	48.5	37.6	31.3	29.1	15.6	
19:00 - 20:00	45.3	69.8	52.0	51.8	48.2	46.5	42.7	40.2	34.4	31.4	29.5	16.2	
20:00 - 21:00	52.4	83.7	53.6	57.1	57.0	50.0	49.4	50.6	36.3	31.1	28.2	15.1	
21:00 - 22:00	49.1	74.4	54.9	56.8	57.4	48.6	48.0	42.6	35.3	31.6	28.9	15.9	
22:00 - 23:00	45.1	71.3	50.0	49.1	45.5	44.1	43.8	40.2	34.0	30.6	28.0	15.0	
NIGHT TIME NOISE LEVELS 23:00 - 07:00 15 MINUTE SAMPLES													
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0 k	2.0 k	4.0 k	8.0 k	16.0 k	
23:00 - 23:15	37.7	55.0	47.5	44.7	36.7	34.8	31.0	31.6	31.3	29.4	27.0	14.7	
23:15 - 23:30	42.8	60.0	50.2	49.7	46.5	44.5	40.4	37.2	32.4	29.2	27.0	14.1	
23:30 - 23:45	44.7	67.3	50.7	50.9	46.6	45.3	43.8	39.3	33.4	29.1	26.5	13.9	
23:45 - 00:00	42.8	60.6	50.3	50.3	44.9	43.2	40.9	38.3	31.9	28.7	26.3	13.6	
00:00 - 00:15	41.9	59.8	48.7	47.5	45.4	43.7	39.1	35.7	32.1	30.5	28.9	15.5	
00:15 - 00:30	45.5	59.5	51.7	49.7	48.8	48.1	44.1	39.5	32.3	30.5	28.7	15.4	
00:30 - 00:45	38.3	56.6	55.0	49.4	34.6	33.2	29.5	32.6	31.5	30.7	29.5	15.9	
00:45 - 01:00	42.0	60.5	50.0	52.5	41.7	34.3	36.9	36.7	34.6	33.0	31.4	17.5	
01:00 - 01:15	35.9	51.2	45.9	42.5	31.4	30.5	25.5	29.0	30.2	28.7	26.6	14.0	
01:15 - 01:30	40.7	59.7	47.0	43.9	49.1	39.2	38.2	33.6	30.6	29.1	27.2	14.3	
01:30 - 01:45	36.2	50.0	46.4	43.1	32.1	31.4	26.0	29.6	30.4	29.0	27.0	14.2	
01:45 - 02:00	38.3	65.6	45.9	42.4	31.5	32.0	30.5	32.1	31.5	31.0	29.7	16.2	
02:00 - 02:15	35.6	50.8	45.7	43.0	31.5	31.1	24.7	28.4	30.0	28.4	26.2	13.8	
02:15 - 02:30	37.0	59.1	47.7	42.8	32.3	31.2	25.4	29.0	31.2	30.5	28.7	18.5	
02:30 - 02:45	36.1	54.5	46.8	42.6	31.3	30.0	24.7	28.5	30.5	29.3	27.3	15.3	
02:45 - 03:00	36.5	57.0	46.7	42.5	32.2	29.4	25.9	29.1	30.5	29.8	28.2	15.1	
03:00 - 03:15	36.1	56.2	46.9	42.5	31.8	30.4	25.4	28.4	30.4	29.3	27.4	14.5	
03:15 - 03:30	39.8	64.1	48.1	42.7	32.8	32.0	27.3	30.6	33.1	34.2	33.4	19.6	
03:30 - 03:45	38.1	64.3	49.2	43.5	33.0	31.6	28.4	30.3	31.8	31.3	30.9	18.2	
03:45 - 04:00	36.5	53.2	49.6	44.2	32.5	31.8	28.9	30.2	30.5	28.7	26.3	14.0	
04:00 - 04:15	35.5	47.8	47.7	43.0	31.9	31.1	25.7	28.6	29.9	28.1	25.4	13.3	
04:15 - 04:30	37.3	57.6	47.2	42.7	31.4	30.2	27.4	30.0	31.4	30.6	29.0	15.7	
04:30 - 04:45	38.0	57.5	48.1	42.9	32.6	30.9	27.8	30.1	32.0	31.4	30.3	16.8	
04:45 - 05:00	36.5	54.3	47.4	43.4	35.3	31.5	26.3	29.3	31.0	29.2	26.7	14.0	
05:00 - 05:15	40.3	58.0	52.8	54.1	48.0	42.2	36.4	32.4	31.2	28.8	26.0	13.7	
05:15 - 05:30	39.1	58.3	48.6	43.8	34.2	33.6	31.6	31.5	32.4	32.3	31.2	17.8	
05:30 - 05:45	36.6	46.9	47.5	43.8	32.3	32.1	29.1	29.9	31.0	28.6	26.0	13.5	
05:45 - 06:00	36.9	45.5	48.7	44.3	33.8	33.1	29.7	30.4	31.0	28.8	26.3	13.7	
06:00 - 06:15	42.7	61.8	51.6	49.5	40.6	39.1	40.3	38.9	33.4	29.6	27.0	14.3	
06:15 - 06:30	43.5	62.0	53.2	52.6	51.6	47.0	40.4	36.3	31.9	29.1	26.4	13.8	
06:30 - 06:45	39.0	55.7	49.7	46.0	35.6	34.0	32.5	34.1	32.0	30.5	28.6	15.4	
06:45 - 07:00	47.2	70.3	52.1	49.2	37.5	38.2	38.6	39.9	33.9	41.7	42.8	19.0	




17.3 17th – 18th November 2018 Position 1

NOISE LEVEL SUMMARY ASSESSMENT				Octave Band Centre Frequency (Hz)									
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0k	2.0k	4.0k	8.0k	16.0k	
DAYTIME 07:00 - 23:00 LAeq 16 HOUR & Corresponding LAmax 16 HOUR	50.1	83.0	58.1	55.7	49.4	47.5	49.0	44.9	38.3	38.5	38.3	21.0	
NIGHTTIME 23:00 - 07:00 LAeq 8 HOUR & Corresponding LAmax 8 HOUR	39.1	71.6	51.1	46.8	40.5	39.4	36.7	34.3	28.6	26.6	23.4	11.1	

DAYTIME NOISE LEVELS 07:00 - 23:00 1 HOUR SAMPLES													
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0 k	2.0 k	4.0 k	8.0 k	16.0 k	
07:00 - 08:00	48.5	71.8	54.6	53.3	47.4	45.7	43.7	42.0	36.4	41.5	42.3	19.0	
08:00 - 09:00	49.8	74.1	54.9	54.2	49.4	46.6	46.8	43.8	37.8	41.6	42.1	19.1	
09:00 - 10:00	48.9	73.1	64.1	56.0	47.0	45.2	46.6	43.4	35.9	40.8	40.3	18.0	
10:00 - 11:00	49.6	76.9	58.1	56.2	48.3	46.2	48.5	44.5	35.2	40.5	39.0	18.3	
11:00 - 12:00	50.9	70.6	61.1	59.7	51.1	48.6	48.7	44.5	40.6	41.1	41.7	26.8	
12:00 - 13:00	50.5	70.8	59.3	57.4	48.7	48.1	49.0	45.0	39.2	40.9	38.6	19.6	
13:00 - 14:00	47.2	66.1	59.4	56.5	47.8	44.4	44.7	42.5	37.9	36.1	32.4	16.5	
14:00 - 15:00	52.2	69.8	60.1	60.1	53.5	49.9	49.6	45.8	42.9	42.4	43.2	28.7	
15:00 - 16:00	51.4	74.0	56.7	55.0	50.3	48.3	50.4	46.1	40.7	37.5	38.5	23.5	
16:00 - 17:00	55.2	83.0	57.9	56.7	51.5	49.6	55.3	50.9	41.1	38.2	37.4	18.7	
17:00 - 18:00	46.4	67.4	54.6	52.8	49.8	47.5	44.1	42.1	34.9	31.0	26.2	13.1	
18:00 - 19:00	50.6	79.3	54.3	52.7	48.9	47.2	51.7	45.4	34.2	26.6	22.6	11.4	
19:00 - 20:00	45.5	71.2	53.9	53.6	48.6	47.0	44.5	40.5	31.6	25.2	20.7	10.9	
20:00 - 21:00	45.6	68.1	52.7	50.2	44.3	43.8	44.7	41.5	33.8	25.9	21.3	11.0	
21:00 - 22:00	49.8	79.3	54.1	52.1	47.8	47.8	49.8	45.5	38.5	30.5	22.0	11.0	
22:00 - 23:00	48.3	73.8	52.9	50.5	49.4	49.7	46.7	43.6	36.9	29.4	23.0	11.3	

NIGHT TIME NOISE LEVELS 23:00 - 07:00 15 MINUTE SAMPLES													
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0 k	2.0 k	4.0 k	8.0 k	16.0 k	
23:00 - 23:15	44.0	66.1	52.4	49.1	40.7	41.3	41.2	41.0	33.9	26.0	21.0	11.0	
23:15 - 23:30	37.7	47.2	51.2	47.1	38.9	37.6	32.9	34.4	28.3	24.3	20.8	10.9	
23:30 - 23:45	39.7	65.5	51.2	46.7	40.6	39.7	37.7	35.2	28.8	24.7	20.8	10.9	
23:45 - 00:00	44.9	71.6	51.9	48.3	38.9	40.6	41.9	42.6	33.4	27.6	27.1	15.2	
00:00 - 00:15	43.7	63.0	52.0	48.7	39.3	40.7	44.2	38.2	32.3	24.8	20.5	10.9	
00:15 - 00:30	36.2	44.6	51.1	46.2	36.2	34.6	31.1	32.4	28.4	24.5	20.1	10.8	
00:30 - 00:45	36.6	48.1	51.0	45.7	36.7	35.7	31.3	32.9	28.3	24.8	20.3	10.9	
00:45 - 01:00	42.1	59.0	54.8	49.3	38.6	38.8	40.5	38.7	31.4	25.1	20.0	10.9	
01:00 - 01:15	35.4	45.4	51.8	46.1	36.1	34.2	30.2	31.2	27.7	24.8	19.1	10.7	
01:15 - 01:30	36.1	45.2	50.9	45.9	36.5	36.1	30.6	31.8	28.2	25.6	20.7	11.1	
01:30 - 01:45	34.3	43.5	50.4	44.8	35.6	33.6	28.3	28.9	27.3	24.8	20.0	10.9	
01:45 - 02:00	34.7	45.0	49.7	44.0	35.4	35.2	28.9	30.2	27.2	24.2	19.5	10.7	
02:00 - 02:15	34.3	44.7	49.7	44.0	35.2	34.6	28.2	29.7	26.8	24.1	19.1	10.7	
02:15 - 02:30	33.4	42.8	49.8	44.6	35.5	33.9	27.1	27.7	26.3	24.1	19.3	10.7	
02:30 - 02:45	34.1	44.9	50.0	44.6	34.4	33.7	27.9	29.6	26.6	24.2	19.3	10.7	
02:45 - 03:00	34.3	43.6	50.5	44.9	34.9	32.9	29.2	29.9	26.5	23.9	19.1	10.6	
03:00 - 03:15	34.4	45.8	50.5	45.2	35.3	33.3	29.1	29.9	26.6	24.2	19.0	10.6	
03:15 - 03:30	33.1	43.8	50.2	44.6	34.6	31.8	26.8	26.8	24.0	18.8	10.5		
03:30 - 03:45	33.0	43.2	51.0	46.5	35.2	32.2	27.2	26.9	26.2	23.6	18.7	10.4	
03:45 - 04:00	33.1	42.5	51.0	46.4	35.0	32.8	28.3	27.0	25.7	23.4	19.6	10.7	
04:00 - 04:15	33.4	49.2	49.2	44.5	34.6	33.5	28.1	27.7	26.1	24.1	19.6	10.6	
04:15 - 04:30	33.4	48.4	49.0	44.3	35.1	33.7	28.6	27.7	25.5	24.4	18.9	10.5	
04:30 - 04:45	34.1	42.6	50.1	43.9	36.1	35.1	29.0	28.8	26.2	24.5	18.4	10.4	
04:45 - 05:00	40.5	60.4	50.5	47.2	45.5	43.7	39.2	34.0	26.9	24.5	18.1	10.3	
05:00 - 05:15	46.4	67.7	55.0	53.0	49.7	49.4	46.2	40.1	26.9	23.8	18.1	10.3	
05:15 - 05:30	34.7	47.7	50.1	44.9	34.9	33.5	29.3	30.7	26.9	23.9	17.8	10.3	
05:30 - 05:45	34.0	51.5	49.4	44.4	34.3	33.3	27.7	28.2	27.0	25.4	21.2	11.1	
05:45 - 06:00	36.9	56.1	52.6	47.7	42.6	39.1	34.0	28.9	27.3	26.3	23.5	12.4	
06:00 - 06:15	36.0	50.5	50.5	46.5	38.4	38.2	31.0	30.3	27.6	25.5	22.5	12.1	
06:15 - 06:30	41.3	57.6	51.7	49.6	48.9	45.9	39.3	32.1	27.8	24.6	19.6	10.8	
06:30 - 06:45	38.2	58.8	51.2	46.7	37.5	38.9	32.4	31.2	27.9	29.4	32.4	12.6	
06:45 - 07:00	41.5	58.2	51.7	47.9	40.6	37.9	30.9	31.8	32.8	37.2	33.3	12.9	




17.4 18th – 19th November 2018 Position 1

NOISE LEVEL SUMMARY ASSESSMENT												
Date / Time	LAEQ	LAMAX	31.5	63	125	250	500	1.0k	2.0k	4.0k	8.0k	16.0k
DAYTIME 07:00 - 23:00 LAEQ 16 HOUR & Corresponding LAMAX 16 HOUR	48.1	75.0	56.8	54.1	49.8	48.8	46.6	42.2	34.1	36.5	36.5	16.5
NIGHTTIME 23:00 - 07:00 LAEQ 8 HOUR & Corresponding LAMAX 8 HOUR	46.6	80.6	54.7	49.3	43.1	44.0	43.5	42.8	38.8	31.4	30.5	16.9

DAYTIME NOISE LEVELS 07:00 - 23:00 1 HOUR SAMPLES												
Date / Time	LAEQ	LAMAX	31.5	63	125	250	500	1.0 k	2.0 k	4.0 k	8.0 k	16.0 k
07:00 - 08:00	48.4	69.4	55.6	53.0	45.4	44.0	42.2	39.5	34.9	43.8	42.3	18.1
08:00 - 09:00	48.6	65.7	55.0	53.2	49.2	48.0	44.5	39.7	35.6	41.5	42.9	19.0
09:00 - 10:00	52.1	75.0	57.6	54.4	51.5	50.9	52.3	46.0	36.2	38.5	39.1	16.2
10:00 - 11:00	48.3	69.8	59.3	57.0	51.6	49.8	46.7	42.5	34.2	35.0	36.9	18.9
11:00 - 12:00	48.5	72.3	58.4	55.9	50.4	49.1	47.0	42.9	35.9	34.7	37.2	18.8
12:00 - 13:00	47.5	66.0	57.9	55.7	50.0	49.2	45.6	41.5	33.2	36.4	35.3	17.0
13:00 - 14:00	47.2	67.6	57.0	53.8	49.7	48.3	45.6	41.8	34.8	34.1	33.6	16.8
14:00 - 15:00	48.4	68.9	59.8	54.5	50.1	49.1	47.2	43.0	34.0	35.2	35.4	19.5
15:00 - 16:00	50.4	72.5	58.0	55.7	51.8	52.9	49.2	44.9	35.7	30.8	34.0	15.9
16:00 - 17:00	47.8	69.6	58.3	56.0	50.2	48.6	45.5	41.6	33.8	39.4	36.8	19.2
17:00 - 18:00	47.6	67.7	55.3	53.1	49.2	48.7	46.9	42.9	33.1	25.4	21.5	11.8
18:00 - 19:00	46.9	68.5	54.9	52.9	49.9	48.3	46.0	42.2	31.9	22.3	17.1	10.5
19:00 - 20:00	43.9	61.8	53.8	51.7	48.7	45.6	42.1	39.5	29.7	22.4	17.3	10.6
20:00 - 21:00	44.1	68.1	54.0	52.4	48.3	46.6	42.7	38.7	29.8	22.5	17.5	10.7
21:00 - 22:00	45.7	70.3	53.5	51.3	48.9	47.8	44.7	40.3	31.2	22.4	16.0	10.4
22:00 - 23:00	46.8	68.7	53.4	51.4	49.1	47.4	45.6	41.9	35.5	27.2	20.6	11.4

NIGHT TIME NOISE LEVELS 23:00 - 07:00 15 MINUTE SAMPLES												
Date / Time	LAEQ	LAMAX	31.5	63	125	250	500	1.0 k	2.0 k	4.0 k	8.0 k	16.0 k
23:00 - 23:15	42.5	61.2	51.5	47.6	47.3	46.6	41.7	34.7	26.6	23.8	21.9	11.8
23:15 - 23:30	48.4	67.1	55.0	54.3	45.6	43.5	44.8	43.8	42.1	35.1	26.7	13.7
23:30 - 23:45	47.8	63.9	51.9	49.6	48.4	49.2	47.4	42.5	34.3	24.1	20.1	11.2
23:45 - 00:00	46.3	76.9	51.7	48.6	38.4	42.3	45.2	43.1	31.5	22.2	16.0	10.3
00:00 - 00:15	44.3	74.3	49.8	45.2	38.0	37.4	33.6	43.7	30.8	21.7	18.0	10.7
00:15 - 00:30	45.6	76.0	50.7	44.7	35.6	35.8	32.9	45.0	33.7	21.9	17.5	10.5
00:30 - 00:45	44.3	62.5	51.3	48.1	42.3	43.4	42.4	41.1	32.4	23.3	18.3	10.7
00:45 - 01:00	37.1	56.8	50.1	45.7	42.8	40.5	36.0	28.6	24.5	21.8	18.5	10.8
01:00 - 01:15	39.1	59.6	49.3	44.7	40.1	41.1	39.3	32.2	24.3	20.7	16.3	10.4
01:15 - 01:30	30.8	40.8	49.5	44.2	33.6	33.0	25.6	23.8	23.7	20.4	14.9	10.3
01:30 - 01:45	31.5	46.0	49.2	44.3	36.3	34.8	26.5	23.8	23.7	20.2	14.2	10.1
01:45 - 02:00	41.2	60.3	51.1	53.5	49.5	45.1	40.0	32.0	24.3	20.2	15.7	10.3
02:00 - 02:15	30.5	45.9	49.3	43.9	33.6	31.9	25.5	23.4	23.8	20.2	14.5	10.1
02:15 - 02:30	30.8	40.2	49.3	44.0	33.9	31.9	26.1	23.4	24.0	20.5	15.5	10.3
02:30 - 02:45	31.5	41.1	48.6	43.9	35.2	33.0	26.5	25.1	24.4	20.1	14.2	10.1
02:45 - 03:00	31.2	39.7	48.6	43.8	33.4	31.7	26.1	24.3	25.1	20.8	14.6	10.1
03:00 - 03:15	31.7	50.8	48.4	43.7	33.4	31.6	26.3	24.1	24.7	23.0	20.8	11.4
03:15 - 03:30	33.7	60.0	51.9	46.6	35.9	33.6	28.3	25.5	26.1	25.2	24.7	13.2
03:30 - 03:45	32.1	45.5	49.1	43.7	33.3	32.2	27.8	24.7	24.8	22.8	20.8	11.3
03:45 - 04:00	34.6	52.7	52.9	45.9	36.7	34.7	29.7	27.5	26.3	26.0	25.6	13.9
04:00 - 04:15	34.3	52.3	50.3	44.8	34.8	33.5	29.5	27.9	26.2	25.5	24.7	13.1
04:15 - 04:30	38.5	56.2	53.6	46.1	38.0	36.3	32.8	30.8	30.0	31.3	31.5	18.5
04:30 - 04:45	35.6	53.2	50.8	45.0	35.5	34.5	31.4	30.4	26.8	26.0	25.3	13.5
04:45 - 05:00	36.2	51.5	51.1	46.2	39.9	36.8	32.2	28.8	27.2	27.0	15.0	
05:00 - 05:15	34.0	46.9	50.3	46.9	34.6	33.9	30.7	29.6	24.6	21.2	17.7	10.6
05:15 - 05:30	43.0	66.0	53.6	49.0	45.6	44.5	41.6	37.4	29.1	28.9	28.7	15.9
05:30 - 05:45	41.2	55.4	55.3	48.7	40.7	39.6	37.0	35.4	32.2	32.3	32.3	19.0
05:45 - 06:00	40.5	56.8	57.0	48.8	39.9	38.9	37.4	35.9	30.6	29.5	29.2	16.3
06:00 - 06:15	48.9	63.5	57.3	51.9	45.2	46.3	44.5	45.0	41.6	34.4	34.3	20.8
06:15 - 06:30	54.6	68.5	58.1	54.0	47.7	50.1	50.0	51.0	47.7	36.7	35.7	21.9
06:30 - 06:45	55.0	72.0	61.1	54.0	47.1	50.3	50.7	51.2	48.0	38.4	38.3	24.8
06:45 - 07:00	56.1	80.6	64.0	56.0	48.1	52.8	53.8	51.5	47.9	41.9	41.4	25.7




17.5 19th – 20th November 2018 Position 1

NOISE LEVEL SUMMARY ASSESSMENT				Octave Band Centre Frequency (Hz)									
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0k	2.0k	4.0k	8.0k	16.0k	
DAYTIME 07:00 - 23:00 LAeq 16 HOUR & Corresponding LAmax 16 HOUR	54.5	80.3	62.6	59.0	51.1	52.2	51.7	50.4	46.2	39.1	39.6	24.2	
NIGHTTIME 23:00 - 07:00 LAeq 8 HOUR & Corresponding LAmax 8 HOUR	46.3	79.7	53.7	49.7	42.7	44.1	43.0	42.9	38.0	28.5	25.6	13.4	

DAYTIME NOISE LEVELS 07:00 - 23:00 1 HOUR SAMPLES													
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0 k	2.0 k	4.0 k	8.0 k	16.0 k	
07:00 - 08:00	55.0	70.6	64.8	56.6	51.2	51.5	50.5	51.2	47.9	37.0	41.2	21.3	
08:00 - 09:00	55.2	71.0	66.1	57.6	50.8	52.1	51.2	51.4	47.9	38.2	38.4	18.0	
09:00 - 10:00	56.0	76.0	62.0	59.1	52.3	53.7	52.7	52.0	47.9	38.9	40.9	19.4	
10:00 - 11:00	55.6	73.9	62.6	63.0	52.0	53.5	52.1	51.4	47.9	39.3	39.2	19.1	
11:00 - 12:00	56.3	78.4	63.2	65.3	51.2	53.2	54.6	51.9	47.7	37.2	37.6	20.2	
12:00 - 13:00	55.8	74.7	62.3	57.2	51.7	54.0	52.9	51.8	47.7	37.6	38.2	21.9	
13:00 - 14:00	55.9	75.2	61.7	57.8	51.3	53.5	52.6	51.9	47.9	37.5	39.7	21.9	
14:00 - 15:00	55.7	76.5	63.2	59.5	51.4	53.3	52.6	51.7	47.7	35.4	34.9	17.6	
15:00 - 16:00	56.2	75.7	67.4	58.9	51.8	53.7	52.9	52.1	48.1	39.8	39.0	24.1	
16:00 - 17:00	54.3	74.1	62.9	56.8	48.4	50.9	49.2	49.6	46.6	44.1	44.3	30.7	
17:00 - 18:00	53.1	74.3	59.0	58.1	53.0	51.4	50.6	47.3	42.4	43.4	44.0	30.8	
18:00 - 19:00	52.0	77.7	57.4	54.5	50.6	50.5	50.3	46.8	40.9	39.9	39.4	25.1	
19:00 - 20:00	50.3	73.1	56.7	54.5	50.2	50.2	49.3	46.0	36.6	28.9	25.4	12.9	
20:00 - 21:00	50.3	72.1	56.3	53.3	48.7	48.8	48.6	45.0	39.5	39.2	38.1	23.6	
21:00 - 22:00	52.0	80.3	56.0	52.9	48.9	49.3	51.8	47.3	37.4	30.0	27.4	14.5	
22:00 - 23:00	48.2	75.5	54.3	51.9	49.0	47.7	46.2	45.1	34.3	28.4	20.7	10.9	

NIGHT TIME NOISE LEVELS 23:00 - 07:00 15 MINUTE SAMPLES													
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0 k	2.0 k	4.0 k	8.0 k	16.0 k	
23:00 - 23:15	44.7	63.9	52.8	49.5	48.2	47.4	43.5	39.4	27.4	25.0	19.5	10.9	
23:15 - 23:30	47.2	75.7	52.6	50.7	46.6	47.1	47.0	41.9	30.3	24.3	17.5	10.4	
23:30 - 23:45	38.5	58.1	51.6	47.1	38.6	38.0	35.4	35.2	26.7	24.8	19.0	10.7	
23:45 - 00:00	45.0	70.9	52.3	48.3	42.2	45.0	44.5	39.9	32.2	25.0	19.8	10.9	
00:00 - 00:15	35.7	50.3	52.2	46.2	37.8	35.7	32.0	30.6	25.6	25.9	23.5	12.5	
00:15 - 00:30	34.1	46.9	52.5	46.0	36.1	34.9	30.1	29.6	23.6	23.9	19.5	10.8	
00:30 - 00:45	34.9	46.3	51.9	46.1	35.1	34.0	31.4	31.3	23.8	23.3	17.6	10.4	
00:45 - 01:00	44.8	66.4	53.9	55.8	43.8	37.6	41.4	41.2	37.4	29.7	19.1	10.4	
01:00 - 01:15	33.2	43.1	52.3	46.7	34.8	34.0	28.6	27.7	23.7	24.5	20.1	11.0	
01:15 - 01:30	35.3	47.2	52.1	45.9	36.5	34.3	29.5	28.7	26.7	28.1	26.2	13.8	
01:30 - 01:45	33.6	47.1	51.9	45.5	36.0	34.1	29.2	27.2	24.3	25.4	22.5	11.9	
01:45 - 02:00	43.0	57.0	55.7	48.4	41.1	38.2	33.0	33.3	35.5	37.4	36.7	23.1	
02:00 - 02:15	36.7	55.1	51.5	46.8	42.4	39.6	33.9	28.9	25.0	25.8	24.2	12.2	
02:15 - 02:30	32.8	45.2	50.7	44.9	33.6	32.7	28.7	27.6	23.2	23.7	20.1	10.6	
02:30 - 02:45	32.0	44.4	51.0	45.1	34.7	33.7	27.2	25.4	22.6	23.6	19.0	10.7	
02:45 - 03:00	31.8	43.3	50.3	44.6	34.2	32.6	27.1	25.7	22.7	23.4	17.5	10.4	
03:00 - 03:15	32.4	42.0	50.3	44.8	34.7	33.2	27.8	26.8	23.2	23.8	18.5	10.6	
03:15 - 03:30	32.7	43.2	51.3	46.1	37.2	34.7	27.8	26.0	22.9	24.0	18.8	10.7	
03:30 - 03:45	33.0	45.9	51.7	46.5	35.7	33.5	28.7	27.4	23.4	24.0	19.3	10.9	
03:45 - 04:00	34.1	56.9	50.1	44.6	34.3	33.7	28.8	28.3	24.8	26.0	25.0	14.6	
04:00 - 04:15	33.5	45.4	50.9	45.6	36.8	33.9	29.1	28.2	23.7	24.2	19.8	11.0	
04:15 - 04:30	39.8	54.9	54.5	48.0	37.4	36.2	33.4	32.0	32.1	33.4	32.1	18.2	
04:30 - 04:45	35.5	47.5	52.7	46.1	36.3	34.9	32.1	30.0	25.9	26.2	24.2	12.3	
04:45 - 05:00	34.2	46.9	51.1	45.6	34.4	33.6	31.5	29.6	23.8	24.0	20.5	10.7	
05:00 - 05:15	35.0	44.5	52.4	47.0	35.6	33.8	32.5	30.6	24.0	23.7	18.1	10.3	
05:15 - 05:30	34.6	44.5	50.7	45.8	35.1	33.9	30.8	30.9	23.9	23.6	17.2	10.2	
05:30 - 05:45	37.9	53.4	52.2	47.8	40.0	41.3	35.0	32.7	25.6	24.5	20.2	10.8	
05:45 - 06:00	37.5	50.0	54.0	48.5	38.5	36.3	34.0	33.8	26.9	25.9	22.8	12.1	
06:00 - 06:15	52.0	65.3	52.1	49.2	42.2	44.7	44.2	50.8	411	28.1	24.9	12.6	
06:15 - 06:30	54.5	69.3	56.2	54.5	45.7	49.6	49.8	51.2	47.3	32.8	26.3	10.9	
06:30 - 06:45	54.2	62.1	59.9	56.0	46.7	49.8	49.1	51.0	47.3	31.1	26.2	11.6	
06:45 - 07:00	56.2	79.7	60.2	56.5	52.9	55.5	54.2	52.0	47.4	32.8	26.6	11.6	



17.6 15th – 16th November 2018 Position 2

NOISE LEVEL SUMMARY ASSESSMENT												
Date / Time	LAEQ	LAmax	31.5	63	125	250	500	1.0k	2.0k	4.0k	8.0k	16.0k
DAYTIME 07:00 - 23:00 LAEQ 16 HOUR & Corresponding LAmax 16 HOUR	54.8	78.2	27.0	37.4	39.4	45.0	48.9	51.0	49.0	42.3	40.7	15.9
NIGHTTIME 23:00 - 07:00 LAEQ 8 HOUR & Corresponding LAmax 8 HOUR	42.9	76.0	14.6	24.9	25.4	30.8	36.7	39.2	37.0	31.3	28.6	8.8
DAYTIME NOISE LEVELS 07:00 - 23:00 1 HOUR SAMPLES												
Date / Time	LAEQ	LAmax	31.5	63	125	250	500	1.0 k	2.0 k	4.0 k	8.0 k	16.0 k
07:00 - 08:00	56.2	78.2	26.4	37.0	39.3	50.5	51.1	49.3	47.5	40.3	38.0	12.8
08:00 - 09:00	56.8	73.1	27.4	36.3	36.4	43.3	49.1	52.4	51.5	43.7	44.3	15.5
09:00 - 10:00	56.9	74.1	28.6	37.8	37.9	44.1	49.5	52.6	51.3	43.9	41.9	16.9
10:00 - 11:00	53.7	66.6	26.2	35.3	35.6	40.9	46.7	49.9	47.6	39.8	37.1	15.1
11:00 - 12:00	54.6	70.5	26.3	36.3	40.4	45.4	48.5	49.8	47.2	40.3	38.6	12.4
12:00 - 13:00	55.8	77.4	25.3	36.2	44.6	47.2	50.5	50.6	47.6	39.4	36.9	11.7
13:00 - 14:00	55.3	74.2	25.6	37.4	39.8	45.9	49.3	50.4	47.8	41.8	40.3	14.1
14:00 - 15:00	53.1	68.3	24.6	34.9	36.1	41.1	46.1	48.6	46.9	41.0	38.7	13.3
15:00 - 16:00	54.3	73.0	26.2	37.4	37.3	42.7	47.3	49.8	47.8	42.6	40.3	15.0
16:00 - 17:00	55.3	69.8	27.4	39.0	41.4	43.8	48.7	50.9	48.7	42.0	39.6	15.1
17:00 - 18:00	55.8	70.4	28.5	38.7	37.8	42.3	48.1	51.3	49.5	44.9	45.0	22.1
18:00 - 19:00	55.6	71.9	27.8	38.4	38.7	42.9	48.4	51.5	49.6	42.9	39.8	15.5
19:00 - 20:00	54.3	67.4	26.8	37.0	35.2	41.1	47.2	50.4	48.2	40.9	38.2	12.8
20:00 - 21:00	51.4	67.7	22.1	32.2	31.0	38.6	44.6	47.7	45.1	38.0	35.0	10.6
21:00 - 22:00	50.7	69.3	22.9	34.3	31.8	37.8	44.0	46.7	44.2	37.9	34.4	10.3
22:00 - 23:00	48.7	67.2	20.6	31.4	30.3	35.7	41.5	44.6	42.8	35.7	32.6	10.0
NIGHT TIME NOISE LEVELS 23:00 - 07:00 15 MINUTE SAMPLES												
Date / Time	LAEQ	LAmax	31.5	63	125	250	500	1.0 k	2.0 k	4.0 k	8.0 k	16.0 k
23:00 - 23:15	49.9	76.0	14.9	26.7	26.3	34.9	42.4	45.0	43.4	41.6	39.0	13.2
23:15 - 23:30	47.3	68.0	16.9	28.6	29.2	34.5	41.1	43.2	40.9	33.8	29.1	8.1
23:30 - 23:45	48.2	64.8	18.7	27.1	28.3	35.5	41.2	44.4	42.0	34.9	31.8	9.0
23:45 - 00:00	46.0	67.5	12.7	28.4	26.1	33.3	39.4	41.6	39.7	34.4	32.0	9.0
00:00 - 00:15	45.1	63.8	17.1	26.6	26.0	32.8	38.5	41.2	38.9	30.9	27.5	8.1
00:15 - 00:30	44.9	65.7	17.5	28.9	30.9	32.0	38.2	40.7	38.3	31.1	28.3	9.9
00:30 - 00:45	44.5	65.3	17.0	29.4	29.8	32.2	39.0	40.1	37.1	29.1	26.6	7.8
00:45 - 01:00	39.1	56.6	9.4	21.6	21.7	28.6	33.3	36.4	25.9	19.2	18.5	7.5
01:00 - 01:15	41.3	64.4	16.6	21.7	23.2	29.2	34.3	37.3	35.4	27.4	22.2	7.5
01:15 - 01:30	38.7	59.3	11.4	22.0	19.8	24.9	32.8	35.7	30.5	22.5	19.5	7.4
01:30 - 01:45	33.0	47.4	9.6	21.5	19.6	22.6	27.3	29.7	19.8	14.9	13.9	7.4
01:45 - 02:00	40.8	66.0	12.6	23.4	24.2	26.5	31.8	34.9	37.3	29.3	23.2	7.5
02:00 - 02:15	34.4	51.0	8.8	21.4	18.0	21.5	28.7	31.8	21.0	14.6	13.9	7.4
02:15 - 02:30	36.0	55.9	6.1	17.8	16.4	21.9	30.5	33.7	22.7	18.3	17.5	7.4
02:30 - 02:45	31.6	46.2	6.2	15.5	15.1	21.3	26.1	27.9	19.3	18.9	18.2	7.5
02:45 - 03:00	33.1	44.5	5.5	15.8	16.5	22.3	26.5	26.3	23.3	25.7	25.3	8.1
03:00 - 03:15	32.9	50.5	6.1	17.3	16.8	23.4	27.0	28.5	21.1	22.0	21.4	7.6
03:15 - 03:30	34.2	49.0	7.0	17.3	17.7	22.5	28.0	30.9	22.3	22.3	21.7	7.6
03:30 - 03:45	34.0	50.2	10.7	21.5	20.2	22.8	29.4	30.1	20.7	16.1	15.0	7.4
03:45 - 04:00	37.4	59.3	10.2	20.3	20.9	25.6	29.8	32.0	32.6	25.7	24.0	8.2
04:00 - 04:15	38.9	61.1	10.6	19.7	21.1	28.9	31.9	34.4	33.1	25.4	22.3	7.6
04:15 - 04:30	41.4	63.9	9.0	23.3	22.1	27.8	34.5	36.8	35.1	30.8	29.8	9.1
04:30 - 04:45	33.8	46.9	9.6	23.0	23.0	23.7	26.9	27.9	22.7	24.3	23.8	7.8
04:45 - 05:00	33.6	45.5	10.6	22.1	21.5	23.7	27.4	28.9	21.9	22.3	21.2	7.6
05:00 - 05:15	34.0	43.6	11.7	23.0	21.4	23.9	27.4	28.5	22.8	24.3	23.7	7.8
05:15 - 05:30	39.1	60.7	15.8	21.9	21.9	27.9	31.9	34.8	33.6	24.7	19.9	7.5
05:30 - 05:45	40.0	61.2	10.6	20.9	19.9	26.9	33.7	36.2	33.2	26.5	24.8	8.0
05:45 - 06:00	40.5	61.4	13.0	22.3	19.5	28.2	33.8	36.7	34.5	25.0	21.7	7.6
06:00 - 06:15	43.3	61.7	16.5	24.6	21.6	29.4	36.1	39.3	37.6	29.7	27.8	8.4
06:15 - 06:30	44.3	64.7	15.7	24.1	25.9	32.4	37.6	40.8	37.4	29.2	27.7	7.8
06:30 - 06:45	46.2	64.0	18.4	27.0	26.6	33.4	39.4	42.2	40.4	32.6	29.9	8.7
06:45 - 07:00	47.8	61.5	18.1	27.2	31.6	36.9	41.1	43.4	41.9	33.9	30.4	8.7

Daytime & Night Time Noise Levels

Daytime & Night Time Noise Levels


Y-axis: LAeq dB (0.0 to 90.0)

X-axis: Time (1 Hour Daytime & 15 Min Night Time Samples)

Legend: LAeq dB (Blue), LAmax dB (Red)

17.7 16th – 17th November 2018 Position 2

NOISE LEVEL SUMMARY ASSESSMENT												
Date / Time	LAEQ	LAMAX	31.5	63	125	250	500	1.0k	2.0k	4.0k	8.0k	16.0k
DAYTIME 07:00 - 23:00 LAEQ 16 HOUR & Corresponding LAMAX 16 HOUR	54.7	84.0	27.0	37.6	40.5	44.4	49.1	50.5	48.9	43.5	41.3	18.5
NIGHTTIME 23:00 - 07:00 LAEQ 8 HOUR & Corresponding LAMAX 8 HOUR	44.5	78.3	18.4	29.9	32.4	34.9	39.0	40.8	38.6	32.0	29.9	9.7
DAYTIME NOISE LEVELS 07:00 - 23:00 1 HOUR SAMPLES												
Date / Time	LAEQ	LAMAX	31.5	63	125	250	500	1.0 k	2.0 k	4.0 k	8.0 k	16.0 k
07:00 - 08:00	52.2	71.1	24.8	33.4	39.9	43.1	45.1	47.5	45.3	38.3	36.4	12.5
08:00 - 09:00	55.0	70.3	26.9	35.8	35.7	41.4	47.9	50.8	48.9	42.1	42.3	14.7
09:00 - 10:00	56.0	71.8	27.4	37.0	37.5	42.5	48.9	51.6	50.1	43.6	42.9	15.5
10:00 - 11:00	53.3	76.0	25.5	34.9	34.4	40.0	45.7	49.0	47.6	41.5	39.9	18.8
11:00 - 12:00	56.2	84.0	25.2	34.8	35.9	43.3	49.8	51.0	51.2	44.3	40.3	25.1
12:00 - 13:00	54.2	82.8	26.2	36.7	35.9	40.2	45.9	49.0	47.9	47.2	40.6	20.2
13:00 - 14:00	53.4	65.8	25.7	35.2	34.8	40.4	46.0	49.1	47.1	42.2	40.8	17.0
14:00 - 15:00	55.9	77.4	27.9	38.0	41.0	47.7	50.5	49.3	48.0	44.1	43.2	18.6
15:00 - 16:00	55.5	79.6	26.9	37.7	37.1	42.8	48.3	50.7	49.5	44.3	42.6	17.8
16:00 - 17:00	55.6	73.5	26.9	38.7	38.7	43.5	48.8	50.8	49.0	44.3	42.6	16.9
17:00 - 18:00	55.9	74.9	27.4	39.3	42.3	45.5	49.9	50.8	49.0	42.8	40.4	15.0
18:00 - 19:00	54.5	67.8	27.9	36.8	36.7	41.9	47.5	50.1	48.4	42.0	40.0	15.0
19:00 - 20:00	53.5	71.0	26.6	36.7	37.2	41.2	46.5	49.2	47.4	40.5	38.1	12.7
20:00 - 21:00	51.7	66.3	24.4	33.6	32.8	38.8	45.0	48.0	45.3	37.6	34.8	12.8
21:00 - 22:00	52.3	80.8	22.6	33.1	37.0	44.6	46.1	47.5	44.6	37.5	34.5	10.6
22:00 - 23:00	56.1	83.5	20.6	39.7	47.7	47.9	52.4	48.4	43.7	38.3	35.7	11.8
NIGHT TIME NOISE LEVELS 23:00 - 07:00 15 MINUTE SAMPLES												
Date / Time	LAEQ	LAMAX	31.5	63	125	250	500	1.0 k	2.0 k	4.0 k	8.0 k	16.0 k
23:00 - 23:15	47.2	65.4	20.3	30.3	28.8	34.3	40.9	43.9	39.6	31.1	28.5	8.9
23:15 - 23:30	53.4	78.3	17.7	41.2	45.1	45.6	47.6	46.6	43.7	37.6	34.0	9.7
23:30 - 23:45	47.1	65.3	21.5	28.6	27.9	34.9	40.5	43.0	41.0	34.0	31.0	8.7
23:45 - 00:00	48.2	66.5	18.7	28.8	28.8	35.5	41.3	44.1	42.1	35.1	31.6	9.1
00:00 - 00:15	46.3	65.8	16.9	26.6	26.4	32.6	39.4	43.0	39.6	31.7	27.8	8.4
00:15 - 00:30	44.6	63.9	16.1	26.7	27.7	31.2	38.5	41.6	35.8	28.1	26.4	8.3
00:30 - 00:45	47.5	65.7	20.7	29.5	32.0	35.7	40.4	43.0	41.6	34.4	33.0	10.3
00:45 - 01:00	44.8	63.9	16.0	25.3	26.0	32.0	38.2	40.7	38.6	31.3	28.9	8.6
01:00 - 01:15	45.4	62.4	17.6	30.1	26.9	33.8	38.5	40.7	39.6	33.1	30.9	9.1
01:15 - 01:30	44.4	64.9	17.3	25.7	25.7	31.9	37.3	40.1	38.7	31.3	29.6	9.1
01:30 - 01:45	43.3	63.3	16.8	25.2	23.4	31.6	37.5	39.1	36.3	29.5	27.6	8.4
01:45 - 02:00	47.0	63.9	20.3	26.9	28.7	34.6	39.6	42.1	42.1	34.9	32.9	9.6
02:00 - 02:15	44.9	63.9	20.3	24.7	23.3	31.8	37.9	41.2	38.9	30.5	28.7	8.8
02:15 - 02:30	40.3	59.7	16.0	23.7	25.0	28.3	33.4	35.4	34.4	27.9	25.8	8.2
02:30 - 02:45	36.8	53.4	14.7	25.5	24.9	25.0	30.3	33.1	25.1	23.4	22.6	7.7
02:45 - 03:00	36.8	53.0	14.7	22.3	22.8	25.6	30.3	32.9	25.8	25.2	24.7	7.9
03:00 - 03:15	37.4	55.2	12.8	20.7	19.7	23.0	27.7	35.4	24.6	25.6	25.4	8.1
03:15 - 03:30	36.1	50.7	15.9	21.5	22.1	25.2	28.6	32.6	24.1	25.2	25.0	8.0
03:30 - 03:45	43.5	69.0	16.4	22.9	22.4	28.1	34.4	37.4	40.1	32.7	29.7	8.7
03:45 - 04:00	33.8	47.1	16.3	22.3	19.7	22.5	27.9	30.5	21.4	15.0	14.4	7.4
04:00 - 04:15	37.3	57.5	15.3	22.1	21.9	26.8	33.0	33.1	26.4	16.4	14.1	7.4
04:15 - 04:30	39.2	62.1	14.6	22.5	20.6	26.9	32.5	34.7	33.0	27.2	24.2	7.8
04:30 - 04:45	31.7	41.9	10.3	20.8	17.8	21.7	26.6	27.2	18.6	17.3	17.3	7.5
04:45 - 05:00	31.9	44.1	10.3	19.4	18.0	23.8	28.2	26.2	16.1	15.1	14.7	7.4
05:00 - 05:15	40.8	63.9	13.1	23.2	21.8	28.2	34.9	36.1	34.2	27.9	27.1	8.6
05:15 - 05:30	40.2	60.8	18.5	23.0	21.6	28.8	33.7	34.6	34.9	27.9	25.0	8.1
05:30 - 05:45	42.4	64.1	14.8	23.4	27.6	34.0	37.9	36.5	35.0	25.1	21.8	7.8
05:45 - 06:00	42.0	61.5	16.7	23.7	22.5	30.5	35.9	37.3	36.1	28.4	26.5	8.5
06:00 - 06:15	42.9	63.6	21.3	28.3	27.4	31.3	35.8	37.9	36.0	31.7	31.8	9.7
06:15 - 06:30	41.5	60.0	17.7	25.4	23.8	28.5	32.6	35.3	35.0	33.8	33.3	11.4
06:30 - 06:45	40.9	58.2	15.0	24.7	26.1	32.7	35.0	36.3	32.0	25.6	24.4	7.7
06:45 - 07:00	42.6	60.9	16.0	24.0	25.5	30.6	35.1	37.4	36.8	32.1	31.2	10.9




17.8 17th – 18th November 2018 Position 2

NOISE LEVEL SUMMARY ASSESSMENT				Octave Band Centre Frequency (Hz)									
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0k	2.0k	4.0k	8.0k	16.0k	
DAYTIME 07:00 - 23:00 LAeq 16 HOUR & Corresponding LAmax 16 HOUR	57.2	81.1	24.4	34.6	36.0	40.8	46.3	50.2	51.5	50.8	49.4	23.8	
NIGHTTIME 23:00 - 07:00 LAeq 8 HOUR & Corresponding LAmax 8 HOUR	47.2	73.2	17.4	26.4	25.5	31.7	37.4	41.4	41.7	40.0	38.1	12.8	

DAYTIME NOISE LEVELS 07:00 - 23:00 1 HOUR SAMPLES													
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0 k	2.0 k	4.0 k	8.0 k	16.0 k	
07:00 - 08:00	49.4	65.6	20.4	26.4	27.8	34.0	38.9	42.5	43.0	42.9	42.4	18.1	
08:00 - 09:00	52.9	71.6	22.4	34.1	33.7	37.4	43.0	46.1	46.9	46.4	45.3	18.7	
09:00 - 10:00	56.7	71.9	23.7	33.1	32.1	39.4	46.2	49.8	51.1	50.3	48.9	22.2	
10:00 - 11:00	57.0	70.6	23.9	34.5	36.1	39.9	46.4	50.2	51.4	50.7	49.3	22.7	
11:00 - 12:00	58.1	71.5	25.6	34.7	33.8	40.3	47.0	51.1	52.8	51.9	50.4	25.4	
12:00 - 13:00	59.1	81.1	26.5	35.7	37.8	41.8	48.1	52.2	53.4	53.5	50.8	24.8	
13:00 - 14:00	57.9	73.0	25.7	38.1	39.4	42.9	47.9	51.5	52.3	50.9	49.2	23.2	
14:00 - 15:00	56.6	70.1	26.4	35.3	35.8	42.2	48.0	51.5	50.8	48.0	46.5	20.0	
15:00 - 16:00	56.9	71.6	26.1	37.5	37.9	42.0	47.5	51.5	51.3	48.9	47.5	20.3	
16:00 - 17:00	57.2	72.4	24.8	36.6	39.9	44.0	47.4	50.9	51.4	49.9	48.5	21.9	
17:00 - 18:00	57.7	72.3	26.2	35.6	36.7	41.5	47.2	51.1	52.4	51.0	49.7	23.7	
18:00 - 19:00	57.3	75.1	25.7	34.3	40.0	44.4	46.9	50.5	51.7	50.3	48.7	22.2	
19:00 - 20:00	59.0	75.2	22.9	32.8	32.8	39.4	47.1	50.9	53.4	53.3	52.2	27.2	
20:00 - 21:00	57.2	73.6	22.0	31.7	30.6	37.2	44.7	49.1	51.8	51.6	50.5	25.6	
21:00 - 22:00	59.3	73.5	22.5	31.9	31.5	38.1	45.4	50.0	53.7	54.1	53.4	29.0	
22:00 - 23:00	54.4	72.4	21.0	30.0	30.0	35.3	42.7	46.8	49.0	48.5	47.4	22.3	

NIGHT TIME NOISE LEVELS 23:00 - 07:00 15 MINUTE SAMPLES													
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0 k	2.0 k	4.0 k	8.0 k	16.0 k	
23:00 - 23:15	53.1	69.6	20.0	30.0	29.3	35.9	42.7	46.6	48.0	46.5	44.5	17.8	
23:15 - 23:30	50.4	73.2	21.8	32.3	27.8	32.4	39.2	43.6	44.5	44.1	43.2	16.4	
23:30 - 23:45	52.7	72.8	20.3	31.7	29.0	35.1	42.3	46.1	47.3	46.1	44.3	19.0	
23:45 - 00:00	50.1	71.4	21.8	28.6	28.1	32.9	39.4	44.0	45.1	43.0	41.2	14.7	
00:00 - 00:15	52.0	69.9	22.9	31.2	28.9	35.1	41.6	46.2	47.1	44.4	42.7	16.0	
00:15 - 00:30	50.6	70.4	18.2	28.2	28.1	35.3	40.1	43.9	45.4	43.6	42.2	15.2	
00:30 - 00:45	46.0	66.0	20.0	25.8	24.0	30.9	37.3	41.5	39.7	37.2	35.3	10.6	
00:45 - 01:00	48.6	68.0	18.8	25.8	24.9	32.3	38.9	43.4	43.2	40.6	38.7	12.5	
01:00 - 01:15	48.9	69.4	18.3	25.5	24.8	32.4	38.8	43.0	43.2	41.8	40.3	13.2	
01:15 - 01:30	47.3	67.8	14.5	23.8	24.2	32.7	38.8	42.1	41.3	39.3	37.4	11.5	
01:30 - 01:45	45.3	69.6	13.0	22.8	22.4	29.4	36.5	40.8	39.4	36.9	34.8	10.3	
01:45 - 02:00	44.3	63.9	15.8	24.3	25.4	29.7	36.0	40.6	38.0	33.5	30.9	9.1	
02:00 - 02:15	38.4	52.3	13.3	22.2	22.0	26.2	31.6	35.9	27.9	19.2	19.0	7.5	
02:15 - 02:30	37.5	54.7	13.5	21.1	20.4	24.4	30.9	35.2	26.4	18.4	17.3	7.4	
02:30 - 02:45	41.5	64.1	15.8	22.9	21.4	27.1	33.3	37.1	35.3	32.0	30.3	8.6	
02:45 - 03:00	45.8	65.4	13.7	23.9	20.3	29.1	35.9	40.5	40.0	39.2	35.7	12.3	
03:00 - 03:15	47.3	67.8	14.5	23.8	24.2	32.7	38.8	42.1	41.3	39.3	37.4	11.5	
03:15 - 03:30	50.6	70.4	18.2	28.2	28.1	35.3	40.1	43.9	45.4	43.6	42.2	15.2	
03:30 - 03:45	45.3	69.6	13.0	22.8	22.4	29.4	36.5	40.8	39.4	36.9	34.8	10.3	
03:45 - 04:00	44.2	69.2	15.9	25.6	24.0	28.5	34.7	38.6	38.9	36.9	33.7	10.3	
04:00 - 04:15	43.4	66.1	13.7	24.8	20.0	26.5	35.0	37.8	37.9	35.8	32.8	9.7	
04:15 - 04:30	45.5	66.1	14.3	24.6	21.7	28.8	35.4	40.3	40.0	38.8	34.3	11.0	
04:30 - 04:45	42.9	52.0	11.2	21.8	18.5	26.6	33.5	38.9	33.4	37.5	29.9	11.3	
04:45 - 05:00	45.8	65.4	13.7	23.9	20.3	29.1	35.9	40.5	40.0	39.2	35.7	12.3	
05:00 - 05:15	41.1	50.1	12.5	23.3	19.9	25.6	32.9	36.3	33.0	34.8	30.4	10.4	
05:15 - 05:30	44.3	65.7	16.5	27.7	27.6	33.5	35.4	36.6	37.6	38.0	34.9	11.9	
05:30 - 05:45	39.2	53.8	15.1	22.1	24.9	27.1	31.1	32.4	30.9	32.7	31.2	10.2	
05:45 - 06:00	41.1	60.8	13.6	21.2	21.4	27.0	32.4	35.2	35.0	33.0	32.7	11.0	
06:00 - 06:15	43.5	68.0	16.9	26.7	27.0	34.8	33.4	35.6	38.0	35.7	33.9	10.1	
06:15 - 06:30	34.8	44.9	13.5	20.1	19.2	23.5	28.6	30.4	24.4	24.2	23.6	7.9	
06:30 - 06:45	41.0	62.5	18.1	23.4	25.7	32.7	33.5	35.1	34.3	30.6	29.1	9.5	
06:45 - 07:00	39.5	52.8	19.0	24.4	29.9	32.1	32.7	34.9	27.6	24.1	24.0	8.0	




17.9 18th – 19th November 2018 Position 2

NOISE LEVEL SUMMARY ASSESSMENT				Octave Band Centre Frequency (Hz)									
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0k	2.0k	4.0k	8.0k	16.0k	
DAYTIME 07:00 - 23:00 LAeq 16 HOUR & Corresponding LAmax 16 HOUR	53.1	84.0	25.9	35.2	37.0	41.9	47.4	48.8	47.1	42.4	41.2	17.9	
NIGHTTIME 23:00 - 07:00 LAeq 8 HOUR & Corresponding LAmax 8 HOUR	43.0	72.1	16.6	25.2	28.9	32.2	36.4	39.0	37.5	31.4	30.3	9.6	

DAYTIME NOISE LEVELS 07:00 - 23:00 1 HOUR SAMPLES													
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0 k	2.0 k	4.0 k	8.0 k	16.0 k	
07:00 - 08:00	44.5	64.2	21.7	26.6	29.1	32.3	36.2	38.8	38.4	35.6	35.3	12.2	
08:00 - 09:00	47.5	69.2	21.4	29.0	28.2	34.1	39.5	42.6	41.0	37.5	37.9	12.9	
09:00 - 10:00	50.7	70.6	22.9	32.9	33.2	39.6	43.2	46.1	44.3	39.0	38.5	13.2	
10:00 - 11:00	52.6	74.1	26.0	33.2	32.9	40.6	45.2	47.8	46.4	41.7	41.7	18.0	
11:00 - 12:00	53.0	69.2	25.9	36.2	38.8	41.8	44.9	48.2	46.7	41.9	41.7	17.8	
12:00 - 13:00	53.6	71.6	26.1	35.5	40.3	42.2	45.8	49.1	47.2	41.5	40.5	16.3	
13:00 - 14:00	53.7	72.6	25.6	35.8	36.0	40.7	46.0	49.2	47.5	42.4	41.8	17.7	
14:00 - 15:00	54.3	69.9	25.5	36.7	38.6	43.5	47.0	49.2	47.0	43.8	44.2	20.1	
15:00 - 16:00	54.3	72.8	25.4	38.4	40.0	43.4	46.9	49.2	47.2	43.7	44.0	19.8	
16:00 - 17:00	54.6	70.6	25.7	36.2	39.8	44.1	47.8	50.0	48.1	41.8	40.4	18.4	
17:00 - 18:00	52.2	68.2	24.4	34.5	33.0	39.8	45.0	48.0	46.0	40.5	38.8	13.8	
18:00 - 19:00	53.4	73.8	27.9	34.9	35.3	41.7	48.5	47.9	46.6	40.8	39.1	18.8	
19:00 - 20:00	49.3	65.9	23.4	30.6	29.8	36.3	42.0	45.2	43.5	37.0	34.7	11.2	
20:00 - 21:00	52.5	83.2	24.1	32.5	33.2	39.3	46.1	48.9	45.6	38.2	35.9	13.5	
21:00 - 22:00	58.2	84.0	28.8	35.6	36.5	45.5	54.0	52.0	51.2	47.5	42.9	21.6	
22:00 - 23:00	46.8	65.9	19.0	27.2	27.9	34.0	39.0	42.3	42.0	34.5	30.7	9.1	

NIGHT TIME NOISE LEVELS 23:00 - 07:00 15 MINUTE SAMPLES													
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0 k	2.0 k	4.0 k	8.0 k	16.0 k	
23:00 - 23:15	46.1	68.1	13.3	27.2	27.0	33.0	38.3	42.0	40.9	33.0	30.1	8.4	
23:15 - 23:30	45.0	68.3	17.5	27.9	26.2	33.6	39.3	39.2	37.8	33.2	35.4	9.6	
23:30 - 23:45	43.0	65.0	17.0	26.1	30.5	31.0	35.5	38.2	37.3	30.0	28.1	9.0	
23:45 - 00:00	42.7	63.6	17.0	25.1	26.0	31.2	35.2	38.5	36.8	29.8	26.5	8.0	
00:00 - 00:15	45.0	68.5	16.2	24.5	27.8	32.7	37.4	39.6	39.9	34.5	32.9	10.7	
00:15 - 00:30	37.7	57.0	13.0	21.6	20.4	27.7	32.9	34.5	23.2	15.4	15.4	7.4	
00:30 - 00:45	39.1	61.0	16.3	23.6	21.4	25.6	31.5	35.0	33.4	26.4	22.3	7.7	
00:45 - 01:00	40.4	62.2	14.7	22.3	21.0	27.0	32.5	36.2	35.5	26.0	22.7	7.7	
01:00 - 01:15	35.5	47.6	17.0	23.5	21.7	24.2	30.0	32.1	22.5	17.3	17.3	7.5	
01:15 - 01:30	33.6	46.1	13.1	20.3	18.5	22.9	28.1	30.4	20.4	13.7	15.1	7.4	
01:30 - 01:45	33.4	50.8	11.9	20.3	18.4	22.6	28.1	29.7	20.6	18.1	17.4	7.5	
01:45 - 02:00	39.7	62.4	18.4	20.5	22.7	27.4	31.0	35.1	35.5	25.8	21.3	7.7	
02:00 - 02:15	31.0	41.7	9.5	18.1	17.2	22.9	26.6	26.0	16.9	14.7	14.3	7.4	
02:15 - 02:30	31.7	42.2	11.5	19.3	17.1	22.8	27.1	27.5	17.5	13.6	14.3	7.4	
02:30 - 02:45	43.6	68.4	10.9	21.6	21.0	29.1	35.1	39.8	38.8	29.7	25.0	7.8	
02:45 - 03:00	41.6	63.2	11.7	20.4	22.3	28.2	34.0	37.1	36.4	29.5	27.5	8.5	
03:00 - 03:15	36.5	59.2	9.9	19.2	22.8	29.2	33.8	27.6	21.6	22.6	21.8	7.7	
03:15 - 03:30	34.2	48.5	10.0	19.1	18.0	24.9	29.1	29.8	22.4	21.2	20.6	7.6	
03:30 - 03:45	41.3	64.9	10.9	21.5	20.1	28.5	33.1	36.4	37.1	28.5	25.5	8.0	
03:45 - 04:00	36.7	48.8	11.2	20.3	20.5	26.1	29.4	31.5	27.3	28.2	27.8	8.7	
04:00 - 04:15	36.3	46.5	13.2	20.3	19.9	26.3	29.4	30.6	26.3	28.1	27.5	8.5	
04:15 - 04:30	42.3	61.0	12.3	24.1	28.8	34.4	38.0	33.8	30.3	32.1	32.4	10.8	
04:30 - 04:45	41.5	55.7	14.9	25.2	34.3	35.8	33.8	33.7	28.3	30.1	30.2	9.8	
04:45 - 05:00	36.6	48.4	13.4	20.4	20.2	26.0	29.1	30.8	27.4	28.8	28.6	8.9	
05:00 - 05:15	42.6	62.0	15.9	23.3	24.5	29.8	35.4	37.1	37.1	32.4	31.3	9.6	
05:15 - 05:30	40.8	58.4	15.0	22.4	23.3	31.5	37.0	33.3	29.5	30.5	30.6	9.9	
05:30 - 05:45	40.8	54.2	14.1	22.4	24.9	32.2	33.0	35.3	31.2	32.4	32.1	10.4	
05:45 - 06:00	47.1	65.7	16.5	25.8	25.7	34.3	39.0	42.8	41.7	35.8	34.2	11.2	
06:00 - 06:15	42.0	53.0	16.1	23.9	21.9	30.8	35.4	39.4	31.6	26.5	26.3	8.3	
06:15 - 06:30	44.1	61.2	16.8	25.6	25.7	32.6	37.3	40.9	36.0	29.1	28.5	8.3	
06:30 - 06:45	50.9	72.1	24.5	33.1	40.0	39.4	42.9	46.2	44.9	37.9	36.5	11.2	
06:45 - 07:00	49.7	64.6	20.3	28.2	31.5	37.1	41.8	45.5	44.3	36.6	34.9	11.3	



17.10 19th – 20th November 2018 Position 2

NOISE LEVEL SUMMARY ASSESSMENT												
Date / Time	LAEQ	LAMAX	31.5	63	125	250	500	1.0k	2.0k	4.0k	8.0k	16.0k
DAYTIME 07:00 - 23:00 LAEQ 16 HOUR & Corresponding LAMAX 16 HOUR	54.9	87.6	25.1	35.2	37.5	44.2	47.9	49.6	49.2	46.0	45.4	31.4
NIGHTTIME 23:00 - 07:00 LAEQ 8 HOUR & Corresponding LAMAX 8 HOUR	0.0	0.0	-7.1	-7.1	-7.1	-7.1	-7.1	-7.1	-7.1	-7.1	-7.1	-7.1
DAYTIME NOISE LEVELS 07:00 - 23:00 1 HOUR SAMPLES												
Date / Time	LAEQ	LAMAX	31.5	63	125	250	500	1.0 k	2.0 k	4.0 k	8.0 k	16.0 k
07:00 - 08:00	56.2	78.2	26.4	37.0	39.3	50.5	51.1	49.3	47.5	40.3	38.0	12.8
08:00 - 09:00	56.8	73.1	27.4	36.3	36.4	43.3	49.1	52.4	51.5	43.7	44.3	15.5
09:00 - 10:00	56.5	73.2	28.1	37.4	36.7	43.7	49.1	52.3	51.0	43.3	41.1	14.1
10:00 - 11:00	54.0	68.2	26.3	35.3	34.4	41.6	46.8	49.5	48.7	40.6	38.3	18.6
11:00 - 12:00	55.7	74.5	26.0	35.8	38.7	43.7	48.2	50.2	49.7	46.0	45.3	21.0
12:00 - 13:00	55.4	69.7	25.4	34.7	37.4	43.3	47.4	49.3	48.9	46.8	46.9	23.3
13:00 - 14:00	56.4	78.1	25.6	35.9	39.2	44.5	48.1	50.4	50.0	48.4	46.9	23.3
14:00 - 15:00	56.2	76.7	25.9	36.4	40.5	45.0	50.2	50.5	49.1	45.8	45.3	20.8
15:00 - 16:00	55.1	70.0	27.3	39.0	40.1	44.6	47.6	49.6	48.9	44.4	43.9	19.7
16:00 - 17:00	61.6	87.6	26.9	37.6	42.1	48.5	52.6	54.2	55.6	54.5	53.9	42.7
17:00 - 18:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
18:00 - 19:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
19:00 - 20:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
20:00 - 21:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
21:00 - 22:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
22:00 - 23:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
NIGHT TIME NOISE LEVELS 23:00 - 07:00 15 MINUTE SAMPLES												
Date / Time	LAEQ	LAMAX	31.5	63	125	250	500	1.0 k	2.0 k	4.0 k	8.0 k	16.0 k
23:00 - 23:15	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
23:15 - 23:30	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
23:30 - 23:45	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
23:45 - 00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
00:00 - 00:15	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
00:15 - 00:30	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
00:30 - 00:45	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
00:45 - 01:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
01:00 - 01:15	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
01:15 - 01:30	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
01:30 - 01:45	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
01:45 - 02:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
02:00 - 02:15	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
02:15 - 02:30	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
02:30 - 02:45	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
02:45 - 03:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
03:00 - 03:15	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
03:15 - 03:30	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
03:30 - 03:45	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
03:45 - 04:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
04:00 - 04:15	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
04:15 - 04:30	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
04:30 - 04:45	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
04:45 - 05:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
05:00 - 05:15	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
05:15 - 05:30	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
05:30 - 05:45	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
05:45 - 06:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
06:00 - 06:15	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
06:15 - 06:30	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
06:30 - 06:45	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
06:45 - 07:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0

Daytime & Night Time Noise Levels

Daytime & Night Time Noise Levels

Y-axis: LAeq dB (0.0 to 100.0)

X-axis: Time (1 Hour Daytime & 15 Min Night Time Samples)


Legend: LAeq dB (Blue Line), LAmax dB (Red Line)

17.11 15th – 16th November 2018 Position 3

NOISE LEVEL SUMMARY ASSESSMENT												
Date / Time	LAEQ	LAMAX	31.5	63	125	250	500	1.0k	2.0k	4.0k	8.0k	16.0k
DAYTIME 07:00 - 23:00 LAEQ 16 HOUR & Corresponding LAMAX 16 HOUR	53.0	86.0	57.9	54.9	48.7	46.8	48.4	43.7	41.6	49.5	35.6	22.2
NIGHTTIME 23:00 - 07:00 LAEQ 8 HOUR & Corresponding LAMAX 8 HOUR	42.5	82.3	43.0	42.5	36.9	31.6	30.0	37.2	32.7	38.6	23.4	12.9

DAYTIME NOISE LEVELS 07:00 - 23:00 1 HOUR SAMPLES												
Date / Time	LAEQ	LAMAX	31.5	63	125	250	500	1.0 k	2.0 k	4.0 k	8.0 k	16.0 k
07:00 - 08:00	58.0	76.7	65.6	60.8	54.7	54.4	57.1	49.3	46.7	52.4	39.7	28.2
08:00 - 09:00	56.0	69.7	64.1	60.5	53.5	52.3	54.4	48.3	45.0	50.3	37.2	26.0
09:00 - 10:00	55.6	73.4	62.9	59.4	52.9	51.5	53.7	48.7	44.8	49.8	36.7	26.4
10:00 - 11:00	53.4	72.5	54.6	52.6	48.7	46.4	45.8	44.9	43.4	50.1	36.9	27.8
11:00 - 12:00	50.8	76.4	51.7	51.4	45.5	42.4	42.0	41.2	41.4	47.9	36.0	18.7
12:00 - 13:00	48.4	70.3	52.0	52.2	47.3	44.4	39.4	39.7	39.4	44.7	35.8	17.1
13:00 - 14:00	60.3	86.0	51.2	50.5	43.6	40.1	37.2	39.4	45.3	59.1	43.5	23.4
14:00 - 15:00	49.5	71.7	52.2	51.3	45.5	42.0	38.9	40.7	39.5	46.7	34.1	18.0
15:00 - 16:00	47.8	65.4	55.9	55.6	48.5	43.1	39.6	41.5	39.7	42.9	30.5	17.4
16:00 - 17:00	48.3	69.2	53.2	53.3	46.7	42.1	40.1	43.2	41.0	42.0	31.6	14.8
17:00 - 18:00	46.0	61.0	53.8	53.0	45.9	42.2	39.1	41.5	38.4	38.6	25.5	16.4
18:00 - 19:00	44.5	59.1	51.6	51.4	47.5	40.8	37.9	41.1	36.8	33.6	19.5	12.9
19:00 - 20:00	43.9	59.1	50.0	50.5	44.5	39.9	37.3	40.0	36.2	35.4	21.1	13.4
20:00 - 21:00	42.7	59.6	46.8	48.1	43.0	38.9	36.1	38.3	35.1	35.2	21.5	13.6
21:00 - 22:00	40.4	55.8	47.1	46.9	40.0	36.9	34.1	36.0	33.0	32.3	18.7	12.8
22:00 - 23:00	37.0	55.2	43.9	43.9	38.4	36.6	31.4	32.4	28.4	28.8	17.1	12.7

NIGHT TIME NOISE LEVELS 23:00 - 07:00 15 MINUTE SAMPLES												
Date / Time	LAEQ	LAMAX	31.5	63	125	250	500	1.0 k	2.0 k	4.0 k	8.0 k	16.0 k
23:00 - 23:15	36.3	52.8	45.1	44.4	38.1	32.6	30.2	32.2	28.5	27.4	15.2	12.2
23:15 - 23:30	33.0	43.3	43.0	42.2	36.8	31.2	28.2	29.1	24.3	22.0	13.9	12.2
23:30 - 23:45	31.3	46.3	40.6	41.4	38.6	31.2	27.1	26.5	21.2	20.8	13.6	12.2
23:45 - 00:00	30.1	47.4	42.1	41.9	35.0	29.4	26.1	25.2	20.0	20.6	13.6	12.2
00:00 - 00:15	31.2	53.1	42.0	41.4	35.8	30.8	26.8	26.6	21.0	22.4	14.3	12.3
00:15 - 00:30	30.4	43.7	43.0	43.3	36.2	29.9	26.3	25.3	20.4	20.9	13.7	12.2
00:30 - 00:45	46.0	71.4	42.8	42.1	35.1	29.6	29.1	43.7	39.3	35.9	18.1	12.4
00:45 - 01:00	42.2	68.5	40.2	40.0	35.2	28.9	27.4	39.2	36.4	32.1	15.5	12.2
01:00 - 01:15	28.1	49.3	38.1	37.6	32.4	27.1	24.6	22.8	16.6	20.5	13.7	12.2
01:15 - 01:30	27.4	53.6	37.7	37.0	32.2	25.9	22.9	21.2	16.8	21.0	14.0	12.3
01:30 - 01:45	34.5	54.0	42.0	39.7	34.7	31.7	27.6	29.6	27.9	25.9	14.7	12.3
01:45 - 02:00	27.1	54.8	36.3	38.2	31.4	23.8	18.8	18.0	16.7	23.1	15.1	12.6
02:00 - 02:15	34.8	54.5	35.1	37.3	30.5	23.2	21.7	34.1	20.6	24.0	15.4	13.7
02:15 - 02:30	35.2	56.2	35.3	33.7	29.1	25.3	18.4	26.3	29.3	30.7	14.3	12.5
02:30 - 02:45	50.3	74.0	36.6	32.2	26.0	21.5	32.3	49.3	41.7	33.8	15.9	12.7
02:45 - 03:00	25.1	42.4	37.4	34.4	28.0	23.3	20.7	18.7	14.6	18.7	13.4	12.4
03:00 - 03:15	26.3	42.4	35.7	33.3	29.8	25.1	23.2	19.9	15.0	19.4	13.5	12.5
03:15 - 03:30	27.8	43.8	38.7	36.7	30.5	27.0	25.1	22.4	16.2	19.3	13.3	12.3
03:30 - 03:45	28.5	45.7	39.1	37.5	33.0	27.8	25.7	23.3	17.3	19.3	13.2	12.2
03:45 - 04:00	28.6	50.3	39.6	41.2	37.9	26.5	23.9	22.7	17.7	20.2	13.6	12.3
04:00 - 04:15	28.1	48.1	43.1	39.9	32.6	27.7	24.6	22.1	16.8	20.5	13.6	12.2
04:15 - 04:30	29.3	43.7	37.2	37.2	33.4	29.0	25.3	24.8	18.9	20.2	13.6	12.2
04:30 - 04:45	31.2	50.8	42.2	40.1	40.2	34.7	26.1	24.5	18.5	19.7	13.2	12.0
04:45 - 05:00	32.3	45.2	42.2	40.4	33.0	28.2	26.1	29.4	24.1	21.0	13.4	12.1
05:00 - 05:15	31.4	57.3	41.6	39.9	33.6	28.2	25.6	25.9	22.0	25.4	15.5	12.4
05:15 - 05:30	35.6	59.0	42.5	41.5	34.9	31.3	29.1	30.5	26.9	29.9	18.5	13.0
05:30 - 05:45	44.9	76.5	42.7	43.2	40.2	32.5	38.2	42.1	39.2	29.4	17.4	13.0
05:45 - 06:00	36.8	62.9	42.4	42.6	35.4	31.1	31.4	34.5	28.0	23.8	14.0	12.0
06:00 - 06:15	44.3	71.2	45.5	45.8	39.6	34.8	32.8	35.8	37.5	40.2	24.2	12.7
06:15 - 06:30	41.5	57.7	47.9	47.4	42.3	37.8	35.2	37.3	33.9	33.3	21.8	13.6
06:30 - 06:45	45.6	65.3	48.9	48.1	43.1	38.0	35.7	37.1	34.7	42.8	28.8	17.2
06:45 - 07:00	54.1	82.3	50.8	51.0	43.2	38.3	36.1	38.5	39.1	52.8	37.1	17.0




17.12 16th – 17th November 2018 Position 3

NOISE LEVEL SUMMARY ASSESSMENT				Octave Band Centre Frequency (Hz)									
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0k	2.0k	4.0k	8.0k	16.0k	
DAYTIME 07:00 - 23:00 LAeq 16 HOUR & Corresponding LAmax 16 HOUR	51.7	82.4	52.1	52.3	46.9	42.2	42.1	44.8	42.8	47.8	36.5	16.7	
NIGHTTIME 23:00 - 07:00 LAeq 8 HOUR & Corresponding LAmax 8 HOUR	43.1	74.7	47.3	43.7	38.2	33.9	34.0	36.9	33.5	39.3	25.3	15.6	


DAYTIME NOISE LEVELS 07:00 - 23:00 1 HOUR SAMPLES												
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0 k	2.0 k	4.0 k	8.0 k	16.0 k
07:00 - 08:00	55.9	82.4	51.5	52.6	44.8	39.0	36.9	40.5	39.7	54.5	42.6	17.9
08:00 - 09:00	53.7	76.3	54.2	54.6	47.8	43.3	40.9	44.0	42.3	51.0	43.3	21.5
09:00 - 10:00	54.3	78.3	54.9	54.9	48.2	45.9	41.7	45.0	45.9	51.3	40.0	17.8
10:00 - 11:00	55.3	65.5	54.4	52.2	49.1	45.4	46.9	49.0	49.0	49.8	33.7	17.4
11:00 - 12:00	56.0	79.7	54.5	56.4	54.1	47.7	48.7	49.4	49.1	50.8	35.6	17.9
12:00 - 13:00	49.6	68.0	51.8	51.1	46.0	40.8	40.4	43.6	39.6	45.3	38.8	20.1
13:00 - 14:00	48.3	71.5	52.4	51.7	44.7	39.7	39.4	43.8	39.0	43.3	30.2	14.4
14:00 - 15:00	49.1	68.1	52.0	52.0	45.7	41.7	40.6	42.7	39.4	45.4	31.5	14.4
15:00 - 16:00	51.4	76.4	51.8	51.0	45.3	40.9	38.7	41.7	39.7	49.4	33.3	16.5
16:00 - 17:00	47.8	73.7	51.7	52.0	44.8	40.1	39.4	42.5	38.2	43.0	34.9	15.1
17:00 - 18:00	49.2	60.3	52.8	52.9	45.6	41.5	42.7	47.1	40.4	36.1	21.6	13.4
18:00 - 19:00	47.6	59.3	51.3	52.2	44.9	40.9	40.8	45.2	39.3	35.6	20.9	13.2
19:00 - 20:00	46.3	58.6	50.4	50.4	42.9	38.7	39.7	44.1	37.3	34.7	21.4	14.4
20:00 - 21:00	45.0	59.6	48.1	49.0	41.3	37.4	38.2	42.3	36.7	35.3	21.3	13.5
21:00 - 22:00	44.5	57.8	46.2	46.3	40.4	36.4	37.9	42.1	35.0	35.3	22.4	14.1
22:00 - 23:00	44.4	60.4	46.4	46.6	40.4	37.1	38.1	41.3	35.9	35.5	21.8	13.7

NIGHT TIME NOISE LEVELS 23:00 - 07:00 15 MINUTE SAMPLES												
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0 k	2.0 k	4.0 k	8.0 k	16.0 k
23:00 - 23:15	42.0	54.6	43.8	44.2	36.8	33.5	35.2	39.7	32.7	31.9	19.2	12.9
23:15 - 23:30	42.5	55.6	44.4	43.7	39.2	33.3	35.3	39.8	33.7	34.1	21.6	14.4
23:30 - 23:45	43.5	59.5	47.1	45.9	37.9	35.4	36.4	40.0	34.8	36.6	23.3	14.5
23:45 - 00:00	47.7	73.0	43.6	43.3	37.8	35.8	42.2	44.2	39.6	38.1	24.3	15.7
00:00 - 00:15	43.4	58.2	43.9	43.6	37.5	34.1	36.0	40.6	34.2	35.5	23.0	14.7
00:15 - 00:30	43.4	60.7	44.3	42.8	37.3	34.2	34.7	39.3	34.3	37.8	25.4	16.3
00:30 - 00:45	42.1	59.0	41.9	44.0	42.4	35.1	33.0	36.4	33.2	37.7	25.2	16.0
00:45 - 01:00	44.4	63.1	40.1	40.8	34.8	32.6	34.3	38.2	34.7	40.9	28.5	18.8
01:00 - 01:15	43.3	66.0	39.5	39.6	34.4	31.8	32.6	35.9	33.4	40.2	27.5	17.8
01:15 - 01:30	40.1	62.6	40.7	38.6	32.4	29.5	29.5	32.5	30.5	37.0	24.7	15.7
01:30 - 01:45	43.9	62.8	42.3	41.1	34.7	33.2	33.5	38.1	36.4	39.3	26.4	17.1
01:45 - 02:00	44.4	74.7	39.1	36.5	33.1	30.9	30.9	31.6	34.0	42.3	29.1	19.2
02:00 - 02:15	39.4	64.1	37.3	35.8	30.1	28.3	29.0	32.2	29.8	36.2	23.7	15.2
02:15 - 02:30	41.8	62.9	38.2	36.4	31.4	29.5	29.9	32.9	32.1	39.1	26.5	17.5
02:30 - 02:45	37.3	57.5	38.2	38.5	37.6	34.7	30.9	31.7	26.9	32.3	20.2	13.4
02:45 - 03:00	41.0	68.8	37.8	35.5	30.2	28.0	26.9	26.4	30.8	39.0	26.4	16.9
03:00 - 03:15	38.0	60.4	38.7	37.5	31.2	29.0	28.7	32.1	29.1	33.9	21.3	13.9
03:15 - 03:30	39.3	60.0	37.5	35.8	30.8	29.5	28.0	27.2	29.7	36.9	24.2	15.2
03:30 - 03:45	40.7	66.3	38.6	39.4	31.8	30.4	29.3	30.7	31.7	37.9	24.9	15.7
03:45 - 04:00	37.0	51.0	38.1	37.7	31.6	29.7	29.7	32.4	28.2	31.6	18.7	12.6
04:00 - 04:15	38.7	60.9	39.9	39.2	36.1	31.1	29.6	32.4	29.7	34.6	21.8	14.1
04:15 - 04:30	37.3	57.0	38.8	36.7	31.7	30.2	28.6	26.5	27.9	34.5	21.6	13.9
04:30 - 04:45	41.4	60.0	40.3	38.5	34.4	32.7	31.3	30.3	32.3	38.7	25.2	15.3
04:45 - 05:00	40.8	64.8	41.4	40.7	37.2	37.3	32.0	33.2	32.9	36.6	23.0	13.8
05:00 - 05:15	40.7	55.9	48.0	46.2	43.5	36.7	32.0	33.5	31.3	36.6	22.7	13.6
05:15 - 05:30	45.9	64.7	47.7	43.8	39.0	37.0	35.8	36.3	36.8	43.1	29.8	18.6
05:30 - 05:45	41.5	55.3	47.1	43.3	38.2	34.4	33.8	34.8	32.4	37.6	24.1	14.3
05:45 - 06:00	42.0	57.6	50.7	46.8	42.4	36.1	34.0	36.4	32.5	37.5	24.3	14.6
06:00 - 06:15	41.3	53.1	57.5	49.6	42.0	35.4	33.9	36.5	31.9	36.0	22.5	13.7
06:15 - 06:30	42.9	61.7	54.8	49.6	40.6	36.0	34.8	38.4	35.8	35.9	21.3	13.1
06:30 - 06:45	43.0	55.0	51.3	49.5	44.1	36.9	36.3	37.9	33.6	37.8	24.5	14.4
06:45 - 07:00	50.8	73.2	49.8	47.5	40.6	35.7	36.3	39.7	36.9	49.2	31.8	14.1




17.13 17th – 18th November 2018 Position 3

NOISE LEVEL SUMMARY ASSESSMENT				Octave Band Centre Frequency (Hz)									
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0k	2.0k	4.0k	8.0k	16.0k	
DAYTIME 07:00 - 23:00 LAeq 16 HOUR & Corresponding LAmax 16 HOUR	52.6	79.7	55.7	56.7	51.2	48.9	46.5	47.7	43.6	46.5	32.9	17.3	
NIGHTTIME 23:00 - 07:00 LAeq 8 HOUR & Corresponding LAmax 8 HOUR	43.7	77.9	50.2	47.1	40.5	37.9	36.6	37.8	33.8	39.2	26.8	15.7	
DAYTIME NOISE LEVELS 07:00 - 23:00 1 HOUR SAMPLES													
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0 k	2.0 k	4.0 k	8.0 k	16.0 k	
07:00 - 08:00	53.4	79.7	52.3	50.1	44.4	39.4	39.3	42.5	39.4	51.7	37.8	17.0	
08:00 - 09:00	51.1	65.1	55.3	53.9	45.9	42.7	43.3	46.6	42.5	45.6	32.2	19.7	
09:00 - 10:00	53.9	70.6	57.4	56.4	48.0	44.5	45.7	49.1	46.8	48.0	35.2	20.6	
10:00 - 11:00	54.6	77.5	55.9	57.5	51.9	49.3	47.2	48.9	45.5	50.0	35.7	16.9	
11:00 - 12:00	58.2	72.6	57.3	57.7	53.7	50.2	50.7	52.9	51.2	52.4	37.6	19.8	
12:00 - 13:00	52.8	67.2	57.3	59.0	54.2	52.3	48.2	48.1	42.5	45.1	32.3	18.8	
13:00 - 14:00	52.6	70.2	56.6	58.4	54.4	51.9	48.8	47.9	42.5	44.3	34.8	17.8	
14:00 - 15:00	52.3	71.4	55.7	58.4	54.3	52.3	48.0	47.9	41.8	43.2	31.3	17.7	
15:00 - 16:00	53.6	73.9	58.1	60.6	55.7	53.6	48.6	48.7	44.1	45.7	29.9	16.0	
16:00 - 17:00	52.8	78.5	56.4	59.2	53.1	51.7	48.1	48.4	41.0	46.0	32.4	16.4	
17:00 - 18:00	49.0	57.4	57.0	56.4	48.5	44.7	44.3	46.9	38.4	34.8	21.0	13.2	
18:00 - 19:00	49.0	62.5	53.8	54.8	46.2	44.0	43.9	46.5	38.7	38.2	24.8	15.6	
19:00 - 20:00	50.3	66.1	53.0	54.6	45.8	44.1	47.0	46.9	40.8	40.3	26.3	15.7	
20:00 - 21:00	47.3	62.9	52.4	52.4	45.6	42.8	42.3	43.7	37.3	39.8	26.1	15.6	
21:00 - 22:00	47.1	61.7	53.5	52.0	44.4	42.2	41.7	43.3	37.8	39.8	26.0	15.6	
22:00 - 23:00	46.2	57.9	52.4	51.6	44.2	41.7	40.5	42.7	36.5	38.5	24.6	14.7	
NIGHT TIME NOISE LEVELS 23:00 - 07:00 15 MINUTE SAMPLES													
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0 k	2.0 k	4.0 k	8.0 k	16.0 k	
23:00 - 23:15	44.7	58.5	52.3	50.5	41.9	39.7	39.8	42.4	34.2	32.9	19.3	12.6	
23:15 - 23:30	46.2	58.9	52.7	51.4	42.8	41.1	40.8	43.0	36.9	37.8	23.9	14.6	
23:30 - 23:45	45.3	54.8	51.5	49.6	41.3	39.2	39.5	42.0	34.9	38.2	24.8	15.2	
23:45 - 00:00	44.5	56.0	49.8	48.6	41.8	39.2	39.4	42.2	34.2	32.5	19.1	12.6	
00:00 - 00:15	43.3	56.1	48.7	48.1	40.7	38.8	38.2	40.9	32.9	32.1	18.4	12.3	
00:15 - 00:30	41.3	56.1	48.3	47.3	39.4	38.0	36.8	38.6	30.3	31.3	18.3	12.4	
00:30 - 00:45	43.8	55.6	48.2	46.6	41.8	39.3	37.8	39.3	34.0	37.9	24.2	14.8	
00:45 - 01:00	42.1	55.1	47.6	46.3	39.9	37.5	36.8	38.2	31.7	35.6	22.4	13.8	
01:00 - 01:15	42.5	54.9	48.2	46.5	39.6	37.9	37.0	39.0	32.2	35.1	21.9	13.6	
01:15 - 01:30	43.5	54.8	48.9	48.2	40.6	37.9	37.2	38.2	33.2	38.8	25.6	15.7	
01:30 - 01:45	43.2	53.9	47.9	46.9	39.3	37.2	35.7	36.2	33.7	39.4	25.8	15.5	
01:45 - 02:00	45.9	56.6	47.2	45.7	39.9	38.3	36.4	36.2	36.6	43.0	29.2	17.8	
02:00 - 02:15	44.0	59.6	47.8	44.0	38.9	37.6	35.9	34.5	34.3	41.0	27.6	17.0	
02:15 - 02:30	39.6	49.5	44.9	42.5	36.7	35.4	33.0	33.0	29.9	35.4	21.8	13.3	
02:30 - 02:45	42.2	60.5	47.7	44.0	38.3	36.3	35.5	35.1	31.9	38.6	25.6	16.7	
02:45 - 03:00	44.1	61.1	48.4	45.2	38.6	37.7	36.6	37.4	35.7	39.8	26.5	16.6	
03:00 - 03:15	41.9	56.2	46.0	42.7	37.0	36.0	33.9	33.2	32.3	38.7	25.2	15.2	
03:15 - 03:30	42.0	55.2	46.7	42.9	37.3	36.5	34.8	32.2	32.3	38.9	25.3	15.1	
03:30 - 03:45	43.8	55.5	47.3	43.3	38.0	36.8	35.6	36.0	34.2	40.5	27.0	16.4	
03:45 - 04:00	44.1	53.1	46.8	42.8	37.8	36.8	35.0	34.7	34.9	41.2	27.5	16.5	
04:00 - 04:15	45.2	77.9	45.4	42.7	36.9	36.1	34.3	34.8	35.1	42.6	32.9	21.7	
04:15 - 04:30	42.6	53.9	46.6	42.4	37.3	35.8	33.7	32.5	33.1	39.7	26.1	15.8	
04:30 - 04:45	43.0	56.1	45.9	42.1	36.8	36.0	33.8	33.2	33.8	40.1	26.3	15.7	
04:45 - 05:00	42.3	52.7	45.9	42.2	36.9	36.3	33.8	33.5	32.9	39.1	25.3	15.0	
05:00 - 05:15	41.2	53.1	50.6	45.3	37.1	35.3	33.3	31.5	31.5	38.1	24.5	15.0	
05:15 - 05:30	42.8	53.1	49.5	44.4	37.7	36.3	34.4	33.6	33.3	39.7	26.2	16.0	
05:30 - 05:45	42.2	56.6	50.5	46.5	38.6	36.6	35.3	36.1	32.6	37.9	24.2	14.5	
05:45 - 06:00	42.6	57.9	49.5	46.9	40.2	38.0	35.0	34.2	32.6	39.1	25.7	15.7	
06:00 - 06:15	44.3	60.0	52.8	49.5	46.2	39.8	36.8	37.9	34.4	40.0	26.4	16.0	
06:15 - 06:30	43.1	54.6	56.0	51.2	47.1	40.2	36.4	35.8	32.5	38.8	25.7	15.7	
06:30 - 06:45	45.3	69.4	56.5	51.0	41.6	40.0	37.7	37.9	35.2	41.8	27.5	16.2	
06:45 - 07:00	46.6	62.2	54.1	49.9	41.9	39.5	37.4	38.1	36.7	43.2	35.2	16.8	




17.14 18th – 19th November 2018 Position 3

NOISE LEVEL SUMMARY ASSESSMENT				Octave Band Centre Frequency (Hz)									
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0k	2.0k	4.0k	8.0k	16.0k	
DAYTIME 07:00 - 23:00 LAeq 16 HOUR & Corresponding LAmax 16 HOUR	51.7	77.6	55.3	55.1	51.7	49.4	46.8	46.4	41.8	45.2	34.8	20.4	
NIGHTTIME 23:00 - 07:00 LAeq 8 HOUR & Corresponding LAmax 8 HOUR	44.0	72.2	51.0	48.6	41.3	39.2	38.8	38.8	33.9	38.5	25.2	15.6	
DAYTIME NOISE LEVELS 07:00 - 23:00 1 HOUR SAMPLES													
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0 k	2.0 k	4.0 k	8.0 k	16.0 k	
07:00 - 08:00	49.9	73.0	52.8	49.9	43.1	41.6	40.4	42.0	37.7	47.2	35.3	15.9	
08:00 - 09:00	49.8	67.5	53.1	52.5	45.2	43.0	42.5	44.2	38.0	45.1	41.0	22.3	
09:00 - 10:00	51.1	70.8	55.1	55.2	51.1	48.9	45.8	46.5	40.7	44.4	32.6	18.0	
10:00 - 11:00	51.7	73.3	54.4	55.3	50.6	48.6	45.7	46.6	41.2	45.8	38.5	20.0	
11:00 - 12:00	52.3	77.6	55.2	56.3	52.6	50.1	47.1	47.5	42.6	45.8	32.7	20.0	
12:00 - 13:00	54.0	71.3	55.9	57.4	53.0	50.8	48.3	48.5	43.9	48.6	37.4	23.1	
13:00 - 14:00	53.6	70.4	57.8	57.2	54.1	52.3	49.3	48.7	43.1	46.3	36.3	23.3	
14:00 - 15:00	54.8	69.5	56.9	57.3	55.0	52.8	50.2	48.8	45.4	48.9	35.9	24.2	
15:00 - 16:00	56.9	75.8	59.0	59.2	59.2	56.5	53.2	50.9	48.3	49.0	37.3	24.5	
16:00 - 17:00	50.1	63.1	55.8	56.0	48.6	47.6	46.1	46.2	39.3	42.2	29.2	18.3	
17:00 - 18:00	48.8	58.7	56.3	54.5	49.2	45.0	44.4	45.5	38.3	40.3	26.9	16.6	
18:00 - 19:00	48.7	63.4	53.9	53.0	46.2	43.9	43.7	44.9	40.0	40.7	27.3	17.1	
19:00 - 20:00	48.4	64.6	54.3	52.1	45.2	43.4	43.9	44.1	38.0	42.2	29.2	18.8	
20:00 - 21:00	46.4	61.5	53.6	52.4	45.5	42.6	41.9	43.1	35.9	37.9	25.0	16.0	
21:00 - 22:00	45.3	60.4	51.4	49.8	43.4	41.2	40.4	41.6	34.7	38.2	24.8	15.3	
22:00 - 23:00	44.7	58.9	52.5	49.4	43.0	40.6	39.6	40.6	34.9	37.9	24.7	15.3	
NIGHT TIME NOISE LEVELS 23:00 - 07:00 15 MINUTE SAMPLES													
Date / Time	LAeq	LAmax	31.5	63	125	250	500	1.0 k	2.0 k	4.0 k	8.0 k	16.0 k	
23:00 - 23:15	45.6	59.1	52.2	48.4	41.7	40.6	40.3	42.0	35.8	38.4	24.3	14.4	
23:15 - 23:30	43.0	60.8	51.5	49.1	42.0	38.6	37.0	38.1	33.1	37.3	24.3	15.3	
23:30 - 23:45	41.8	60.4	50.4	47.3	40.3	38.4	37.5	36.7	30.4	36.2	23.2	14.5	
23:45 - 00:00	39.7	51.1	47.9	45.9	39.3	37.9	35.6	34.4	28.0	33.6	20.9	13.4	
00:00 - 00:15	38.8	53.7	49.5	46.9	38.5	36.8	35.0	33.8	27.3	32.2	19.5	12.9	
00:15 - 00:30	39.2	48.5	49.0	47.1	38.9	36.2	34.4	33.5	28.6	33.9	20.5	13.0	
00:30 - 00:45	38.9	53.1	45.3	46.4	37.7	35.6	34.0	32.9	28.1	34.0	20.7	13.1	
00:45 - 01:00	37.3	52.7	46.1	44.3	37.1	35.4	33.8	31.1	25.9	31.7	19.2	12.9	
01:00 - 01:15	36.8	50.5	45.9	43.8	38.3	35.0	32.6	29.6	25.1	32.1	19.8	13.1	
01:15 - 01:30	40.4	55.7	48.9	45.4	39.8	37.3	35.3	33.0	31.1	35.7	22.8	14.5	
01:30 - 01:45	39.7	56.8	47.4	44.0	38.4	36.2	34.2	30.1	29.3	36.2	23.1	14.4	
01:45 - 02:00	43.2	59.2	49.5	44.6	39.7	37.8	37.1	32.4	32.6	40.2	27.3	17.6	
02:00 - 02:15	37.4	57.2	47.6	42.9	36.7	35.0	34.2	30.0	26.3	32.4	20.1	13.4	
02:15 - 02:30	42.8	59.0	49.5	44.4	39.4	37.8	37.4	31.9	32.7	39.6	26.3	16.3	
02:30 - 02:45	46.7	62.2	59.8	55.5	44.7	42.4	43.2	39.8	35.8	41.7	28.8	18.7	
02:45 - 03:00	42.7	58.5	49.4	44.0	39.5	37.5	36.7	30.7	32.5	39.7	26.5	16.5	
03:00 - 03:15	44.2	58.6	50.7	44.8	40.4	38.8	38.5	31.6	34.0	41.3	28.2	18.0	
03:15 - 03:30	41.1	58.5	48.6	45.4	37.8	36.3	35.3	30.6	30.9	37.9	24.8	15.4	
03:30 - 03:45	39.1	50.6	46.5	43.3	36.9	35.1	33.1	29.2	29.1	35.6	22.2	13.7	
03:45 - 04:00	39.3	52.2	47.6	44.1	36.9	35.3	33.5	29.3	29.2	35.9	22.6	13.9	
04:00 - 04:15	41.6	51.9	47.1	43.3	37.9	36.4	35.1	31.7	31.6	38.4	25.0	15.3	
04:15 - 04:30	43.7	56.4	49.9	46.0	40.3	38.2	37.2	32.4	33.9	40.6	27.1	16.7	
04:30 - 04:45	42.3	56.3	48.7	48.2	39.2	36.7	35.7	32.1	32.4	39.2	25.9	15.9	
04:45 - 05:00	40.2	55.2	46.9	47.6	39.6	36.6	35.1	34.3	29.5	35.1	21.9	13.6	
05:00 - 05:15	43.5	52.7	51.2	49.4	40.1	37.7	36.7	36.8	34.2	39.3	25.6	15.4	
05:15 - 05:30	44.4	55.9	50.5	49.4	42.3	39.8	39.4	39.2	34.2	38.9	25.4	15.3	
05:30 - 05:45	44.6	56.8	49.7	49.9	41.9	40.5	41.8	41.0	33.1	35.4	22.2	13.9	
05:45 - 06:00	45.8	59.1	51.0	50.3	43.0	40.8	40.9	42.0	35.5	38.8	25.6	15.7	
06:00 - 06:15	45.6	56.4	50.6	50.8	44.8	40.9	40.9	43.1	34.8	35.2	21.6	13.3	
06:15 - 06:30	46.5	57.2	52.8	51.4	44.3	41.6	41.8	44.1	36.0	35.4	23.3	14.4	
06:30 - 06:45	50.1	72.2	54.7	52.9	46.1	44.0	44.6	46.0	40.4	43.6	30.5	19.6	
06:45 - 07:00	51.4	67.9	54.7	54.5	47.3	46.0	45.5	47.2	42.2	45.1	31.4	20.4	






17.15 19th – 20th November 2018 Position 3

NOISE LEVEL SUMMARY ASSESSMENT				Octave Band Centre Frequency (Hz)									
Date / Time	LAeq	LAmax		31.5	63	125	250	500	1.0k	2.0k	4.0k	8.0k	16.0k
DAYTIME 07:00 - 23:00 LAeq 16 HOUR & Corresponding LAmax 16 HOUR	54.3	80.7		58.6	56.3	54.2	49.5	49.3	48.1	44.6	49.1	36.6	24.1
NIGHTTIME 23:00 - 07:00 LAeq 8 HOUR & Corresponding LAmax 8 HOUR	53.3	74.5		61.0	54.8	50.3	50.0	52.0	41.9	41.4	48.1	35.0	24.2
DAYTIME NOISE LEVELS 07:00 - 23:00 1 HOUR SAMPLES													
Date / Time	LAeq	LAmax		31.5	63	125	250	500	1.0 k	2.0 k	4.0 k	8.0 k	16.0 k
07:00 - 08:00	55.1	73.0		57.0	56.3	49.0	46.8	47.0	48.7	45.9	51.0	40.7	26.2
08:00 - 09:00	54.2	67.2		57.2	57.2	48.5	47.0	47.2	49.2	45.1	49.3	36.3	24.1
09:00 - 10:00	52.4	74.4		56.6	55.4	48.7	45.5	45.8	47.8	42.7	46.9	37.3	20.3
10:00 - 11:00	52.2	67.5		55.0	55.8	58.2	49.1	46.6	47.2	42.2	45.4	32.8	20.3
11:00 - 12:00	55.5	72.7		57.1	56.8	59.1	52.8	49.6	48.5	47.0	50.2	38.6	25.2
12:00 - 13:00	54.1	71.4		59.1	55.9	50.5	49.4	50.3	48.2	43.8	48.8	36.8	24.3
13:00 - 14:00	54.9	74.0		58.6	56.9	49.9	48.0	49.8	47.4	45.6	50.9	37.6	26.2
14:00 - 15:00	55.9	72.1		60.9	58.6	61.8	54.1	52.6	49.0	46.3	49.3	36.3	25.3
15:00 - 16:00	53.8	69.3		58.5	58.7	53.8	51.9	50.3	48.9	44.2	46.1	32.9	21.9
16:00 - 17:00	56.9	80.7		59.4	56.1	51.5	51.6	50.7	45.4	52.9	39.4	24.7	
17:00 - 18:00	53.4	65.8		56.7	56.8	48.6	45.2	46.2	49.6	44.8	47.0	33.8	23.6
18:00 - 19:00	53.0	63.9		55.8	54.7	46.8	44.5	45.9	48.6	44.1	47.3	34.0	22.9
19:00 - 20:00	55.0	68.2		60.3	55.8	49.9	48.7	49.8	47.6	45.6	50.8	37.5	26.3
20:00 - 21:00	51.1	68.8		58.7	54.9	48.6	47.4	48.0	45.4	41.3	44.9	31.7	20.7
21:00 - 22:00	53.8	69.6		61.4	55.4	50.1	49.3	50.9	45.1	44.4	49.0	35.8	24.7
22:00 - 23:00	52.5	68.2		60.3	54.1	49.8	49.1	50.7	43.0	41.5	47.8	34.7	23.7
NIGHT TIME NOISE LEVELS 23:00 - 07:00 15 MINUTE SAMPLES													
Date / Time	LAeq	LAmax		31.5	63	125	250	500	1.0 k	2.0 k	4.0 k	8.0 k	16.0 k
23:00 - 23:15	51.4	65.5		59.7	53.2	49.4	48.5	50.0	41.8	39.8	46.4	33.3	22.3
23:15 - 23:30	52.3	68.4		59.9	54.2	49.2	48.5	50.1	42.5	41.7	47.8	34.6	23.7
23:30 - 23:45	47.9	65.5		56.4	50.5	46.3	45.2	46.2	37.3	36.3	43.3	30.2	19.7
23:45 - 00:00	48.6	63.4		56.4	50.5	46.8	46.1	47.4	38.6	36.8	43.5	30.5	19.9
00:00 - 00:15	50.5	67.6		57.9	51.4	47.7	47.3	49.0	38.1	38.9	46.0	33.0	22.4
00:15 - 00:30	52.7	67.6		60.5	53.8	50.2	49.8	51.7	40.3	40.9	48.1	35.0	24.1
00:30 - 00:45	51.7	62.7		59.8	53.0	49.7	48.8	50.4	38.9	39.9	47.1	33.9	22.9
00:45 - 01:00	53.8	68.0		61.3	54.2	50.5	50.7	52.9	41.0	42.1	49.1	36.0	25.1
01:00 - 01:15	54.4	69.7		62.0	55.0	51.3	51.4	53.5	41.7	42.5	49.6	36.5	25.6
01:15 - 01:30	51.2	63.9		59.7	52.7	49.5	48.6	50.2	38.0	39.4	46.6	33.4	22.4
01:30 - 01:45	51.6	67.6		59.9	53.0	49.4	48.8	50.7	38.5	39.6	46.7	33.6	22.6
01:45 - 02:00	49.5	62.8		57.8	51.0	47.9	46.8	48.3	37.6	37.7	44.7	31.5	20.7
02:00 - 02:15	55.3	69.4		63.1	56.0	51.9	52.2	54.4	42.4	43.6	50.6	37.5	26.6
02:15 - 02:30	57.0	74.2		64.7	57.8	53.3	53.8	56.2	44.3	45.3	52.2	39.2	28.5
02:30 - 02:45	54.4	72.2		62.5	55.4	51.2	51.1	53.2	42.0	42.9	49.8	36.7	25.8
02:45 - 03:00	53.3	66.6		61.1	54.2	50.9	50.7	52.8	40.1	41.0	48.2	35.1	24.2
03:00 - 03:15	51.6	67.0		59.9	53.1	49.4	48.9	50.6	38.4	39.7	46.9	33.8	23.0
03:15 - 03:30	54.1	70.5		62.1	55.3	51.3	51.0	53.1	41.3	42.4	49.4	36.3	25.4
03:30 - 03:45	55.7	74.5		63.5	56.5	52.4	52.8	55.0	42.5	43.4	50.8	37.6	26.8
03:45 - 04:00	54.1	71.3		61.9	55.0	51.2	51.2	53.0	41.3	42.5	49.5	36.4	25.5
04:00 - 04:15	53.4	69.8		61.5	54.8	50.8	50.7	52.7	40.3	41.3	48.5	35.5	24.7
04:15 - 04:30	53.8	74.0		61.4	54.7	50.3	50.5	52.9	41.4	41.9	49.0	36.0	25.2
04:30 - 04:45	52.8	68.4		61.0	54.5	49.9	49.4	51.3	40.5	41.3	48.4	35.3	24.5
04:45 - 05:00	52.7	67.2		61.1	54.1	50.0	49.5	51.3	40.6	41.3	48.2	35.2	24.4
05:00 - 05:15	56.6	74.2		65.0	58.4	53.1	53.6	56.2	44.7	44.6	51.4	38.4	27.8
05:15 - 05:30	53.4	74.0		61.4	55.2	50.4	50.4	52.5	42.4	41.5	48.3	35.3	24.6
05:30 - 05:45	53.1	65.8		61.4	55.2	51.1	50.5	52.3	42.2	41.1	47.9	34.8	24.0
05:45 - 06:00	53.5	71.2		61.3	56.1	51.1	50.6	52.5	43.9	41.8	48.2	35.0	24.1
06:00 - 06:15	53.3	65.3		60.7	56.0	51.1	50.4	52.1	44.4	42.1	47.8	34.6	23.7
06:15 - 06:30	52.8	67.7		60.9	56.9	51.0	49.8	51.3	45.2	41.6	47.1	34.1	23.3
06:30 - 06:45	50.8	63.9		59.4	56.2	49.1	47.2	48.1	45.6	40.4	44.1	30.8	19.9
06:45 - 07:00	53.6	64.2		62.4	57.9	51.6	50.5	52.1	47.1	42.2	47.2	34.1	23.2




18 ENVIRONMENTAL CONDITIONS







17th November 2018



18th November 2018



#END OF REPORT#